UNITED STATES DEPARTMENT OF THE INTERIOR, Stewart L. Udall, *Secretary*

FISH AND WILDLIFE SERVICE, Clarence F. Pautzke, *Commissioner*

BUREAU OF COMMERCIAL FISHERIES, Donald L. McKernan, *Director*

TANK CULTURE OF TILAPIA

BY RICHARD N. UCHIDA AND JOSEPH E. KING

FISHERY BULLETIN 199

From Fishery Bulletin of the Fish and Wildlife Service

VOLUME 62

PUBLISHED BY UNITED STATES FISH AND WILDLIFE SERVICE • WASHINGTON • 1962

PRINTED BY UNITED STATES GOVERNMENT PRINTING OFFICE, WASHINGTON, D.C.

For sale by Superintendent of Documents, U.S. Government Printing Office, Washington 25, D.C.

Price 30 cents

Library of Congress catalog card for the series, Fishery Bulletin of the Fish and Wildlife Service:

U. S. *Fish and Wildlife Service.*
Fishery bulletin. v. 1–
Washington, U. S. Govt. Print. Off., 1881–19

v. in illus., maps (part fold.) 23–28 cm.

Some vols. issued in the congressional series as Senate or House documents.
Bulletins composing v. 47– also numbered 1–
Title varies: v. 1–49, Bulletin.
Vols. 1–49 issued by Bureau of Fisheries (called Fish Commission, v. 1–23)

1. Fisheries—U. S. 2. Fish-culture—U. S. I. Title.

SH11.A25 639.206173 9—35239*

Library of Congress [59r55b1]

CONTENTS

	Page
Introduction	21
Culture methods	23
Rearing facilities	23
Pilot plant	23
Kewalo plant	24
Stocking the brood tanks	25
Feeding	26
Fry production	27
Fry collection	28
Fry rearing	29
Length-weight relation of young	29
Water-quality determinations	29
Oxygen content	29
Hydrogen-ion concentration	30
Free carbon dioxide	31
Alkalinity	31
Mortalities	31
Among the adults	31
Among the young	31
Disease prevention and control	32
Trichodina spp	32
Chilodon spp	32
Infectious pancreatic necrosis	32
Prophylactic measures	33
Factors affecting fry production	34
Temperature and spawning	34
Sex ratio and brood-stock density	37
Diet and reproduction	38
Salinity and spawning	39
Factors affecting growth of young	40
Concentration of fish and growth	40
Diet and growth	41
Salinity and growth	42
Cannibalism and predation	44
Summary and conclusions	45
Literature cited	46
Appendix	48

ABSTRACT

This study evaluated the feasibility of producing bait-size tilapia by the tank-culture method. Two facilities were used: a pilot plant constructed on the grounds of the Biological Laboratory at Honolulu and a second and more elaborate plant constructed at Kewalo Basin, Honolulu.

Study of some of the factors associated with reproductive rates revealed that (1) only a slight increase in water temperature was necessary to increase spawning frequency during winter months, (2) prolonged high temperatures seemed to have a detrimental effect on spawning fish, (3) a sex ratio of 3♀ : 1♂ resulted in the highest reproductive rate, (4) a concentration of brood stock that allowed 4.0 square feet of bottom area per male and 1.0 square foot per individual provided optimum conditions for courtship and spawning, (5) brood stocks fed a high-quality feed had a higher reproductive rate than those maintained on a low-quality feed, and (6) brood stocks maintained in brackish water of about 10 °/₀₀ had significantly higher fry production than those in fresh water.

Crowding affected growth rate of young as did quality of the food and salinity of water.

The major causes of mortality among the adults were handling, disease, asphyxiation, and possibly hydrogen sulfide poisoning. High mortality rates among the young were caused by an infectious disease and infestation by ectoparasitic protozoans.

Experiments on cannibalism indicated that juvenile tilapia averaging 20.4 mm. killed or consumed fry up to 10.0 mm. in length, while juveniles averaging 64.4 mm. in length were able to kill or consume smaller juveniles up to a maximum size of 24.5 mm. Starved juveniles were more aggressive than well-fed juveniles.

TANK CULTURE OF TILAPIA

By RICHARD N. UCHIDA and JOSEPH E. KING, *Fishery Research Biologists*
BUREAU OF COMMERCIAL FISHERIES

ntil about two decades ago, the cichlid fish *pia mossambica* Peters had received only or attention as a food and game fish in its e East African environment. No intensive vation of tilapia was carried on in Africa, and as not until this fish mysteriously appeared in Java in 1939 that anyone recognized that it essed many of the desirable characteristics of ndfish and that it was readily adaptable to are (Atz, 1954). The potentialities of vari- pecies of *Tilapia* were demonstrated by W. H. ster before a gathering of inland fisheries ex- s held at Surabaja in 1939 (Vaas and Hof- , 1952). Since that time, tilapia have been essfully introduced into many southeastern n countries where they have become an im- ant source of protein food.

recent years, many scientists in various parts e world have studied the biology of tilapia and ulture in ponds and rice paddies. The work of s and Hofstede (1952), Chen (1953), Panik- nd Tampi (1954), and Swingle (1960) is par- arly noteworthy. Chimits (1955, 1957) has ished excellent reviews of tilapia culture and bibliographies bring together a wealth of in- nation on these fishes. Baerends and Baer- -Van Roon (1950) should be mentioned for contributions to knowledge of the behavior he cichlids. Other sources of information on ous aspects of tilapia culture and biology are k (1954), on spawning in salt water; Fish 5) and Le Roux (1956), on feeding habits; Lowe (1955), on fecundity. Brock and ata (1955) and King and Wilson (1957) re- ed on use of young tilapia as supplementary bait, and Hida et al. (1961) on the tank ure of bait-size tilapia.

wingle (1957) was the first to recognize that ies of *Tilapia* have potentialities as a fresh-water game fish in the United States. Other investigators have found several of the many species of *Tilapia* to be suitable laboratory animals for many types of physiological research.

The decision to introduce *T. mossambica* to Hawaii was based primarily on two major considerations: the usefulness of the fish for clearing aquatic vegetation from irrigation ditches and canals and the possibility that the young could be used as bait fish in the Hawaiian skipjack fishery (Brock and Takata, 1955). Since its introduction to Hawaii in 1951, tilapia has received widespread attention and is now well established in many private and commercial ponds throughout the major Hawaiian islands.

The pole-and-line fishery for skipjack (*Katsuwonus pelamis*) is the largest commercial fishery in Hawaii. Descriptions of this fishery and the associated live-bait fishery have been published by June (1951), Brock and Takata (1955), and Yamashita (1958). All of these investigators cite the shortage of bait fish as the principal factor limiting production of this pole-and-line fishery.

Because of this critical demand for bait, attention was focused on tilapia as a possible supplement to natural bait supplies. Tester et al. (1954), experimenting with artificial materials (both edible and inedible) to attract tuna to the stern of a fishing vessel, reported generally negative or inconclusive results, which gave added impetus to the search for a suitable substitute live bait. In the summer of 1954, Brock and Takata (1955) initiated the first sea trials to evaluate tilapia as live bait and in a number of the sea tests they obtained encouraging results. King and Wilson (1957: p. 8) made further sea tests during the summer and fall of 1956 and concluded that the young of *Tilapia mossambica* are an adequate bait fish for catching skipjack. They further pointed out that although tilapia in some respects was in-

proved for publication, November 3, 1960. Fishery Bulle- 99.

ferior to nehu (*Stolephorus purpureus*), the principal bait used in the skipjack fishery, it was on the other hand, hardier than nehu and could tolerate a wider range of salinity and lower oxygen concentrations.

In view of the reported success in using young tilapia as a tuna bait fish, consideration was given to devising rearing methods that would be economically and biologically feasible for producing adequate numbers of fish of proper size. Two immediate possibilities presented themselves: pond culture, whereby existing ponds on the islands would be utilized with some modifications; and tank culture, with separate spawning tanks and fry-rearing or nursery facilities.

King and Wilson (1957: p. 8) utilized bait-size tilapia obtained from private ponds and reservoirs for their sea trials and after a number of bait-seining operations concluded that—

> it does not appear that the rearing of tilapia for bait purposes can be done most effectively in water reservoirs and natural ponds with little control over spawning, cannibalistic traits of the species, and predation, and with the difficulty of harvesting the fish efficiently at an optimum size.

It was anticipated that tank culture of the fish under controlled conditions might prove to be a more efficient and economical way to produce bait-size tilapia. As a result, a study of tank culture of tilapia on a pilot-plant scale was initiated at the Bureau of Commercial Fisheries Biological Laboratory at Honolulu. The primary objectives of this study were to determine the physical and biological problems associated with tank culture and the potentialities of producing bait-size tilapia in sufficient quantities under controlled conditions in a hatchery-type operation.

The pilot plant was constructed on the grounds of the laboratory in October 1956 and experiments were carried on there until July 1958, after which the facilities were transferred to more spacious grounds adjacent to the laboratory's new docksite building at Kewalo Basin, Honolulu. Studies continued at the Kewalo plant until September 1959. While the purpose of the pilot plant was primarily to examine the general problems associated with production of bait-size tilapia, the Kewalo plant studies were designed to obtain a more detailed and quantitative evaluation of tank culture and to assess the various factors associated with variations in reproductive, survival, and growth rates.

The purposes of this report are to discuss our efforts in establishing operational procedures and basic requirements that would be applicable to a commercially operated tilapia hatchery, to present our observations and conclusions on reproduction and growth, and to describe the cannibalism, predation, and diseases of tilapia observed during the experiments.

As work progressed, the need for information on other rearing methods became evident and a study of pond culture of tilapia under controlled conditions was begun by the Hawaii Division of Fish and Game at Kaneohe, Oahu, under contract with the (Territorial) Economic Planning and Coordination Authority (EPCA) and the Bureau of Commercial Fisheries. Production of bait-size tilapia in ponds under uncontrolled conditions was investigated to some extent by King and Wilson (1957) during the summer of 1956.

The Maui Fisheries and Marine Products Co., Ltd., expressed an interest in establishing a tilapia hatchery on a semicommercial basis, following our initial success in producing bait-size tilapia at the pilot plant. A contract was signed with Maui Fisheries, the Hawaii Division of Fish and Game, and the Bureau of Commercial Fisheries, as principals, late in December 1957, for the operation of a tilapia-rearing plant at Paia, Maui. A fishery biologist, supplied by the Bureau, was placed in charge of the plant to obtain detailed records of the production and of operational costs. The Paia hatchery was operated for 2 years and the results have been reported by Hida et al. (1961).

In frequent references throughout this report to the various stages of development of tilapia, we have tried to conform to generally accepted terminology, but in some instances we found combinations of categories more suitable and in other ways we have diverged from ordinary usage. The terminology that we have employed is defined as follows:

Fry.—Includes both the prolarval (yolk-bearing) and postlarval (nonyolk-bearing) stages. Includes tilapia up to 19.0 mm. (0.75 in.) in length.

Juvenile.—Stages between fry and adult, with a range in size from about 20 to 100 mm. (0.75 to 4 in.).

it size.—Juveniles suitable for skipjack bait
e in size from about 38 to 51 mm. (1.5 to 2 in.);
ever, on several occasions juveniles falling out-
this length range have been used for bait.
ung.—A general category that includes fry
juveniles.
Tult.—Mature fish that are potential breeders
are distinguished by the display of coloration,
ially by the males in the reproductive phase.
er than 100 mm. (4 in.) in length.
e length measurement used in this report is
length; that is, the length from tip of the
to ends of the middle caudal rays. Body
surements (length and weight) were made in
English and metric units during the early
es of the investigation. However, all origi-
neasurements in English units have been con-
d to their equivalent in metric units, and
e applicable or when appropriate the Eng-
units are given in parentheses. Reference to
facilities is either to the pilot plant con-
ted on the grounds of the Bureau's Honolulu
ratory or to the Kewalo plant located at
Kewalo Basin docksite.

e gratefully acknowledge the advice and sug-
ons given us by the Bait-fish Research Co-
nating Committee composed of biologists of
Hawaii Division of Fish and Game, the Uni-
ty of Hawaii, and the Bureau of Commercial
eries, Honolulu, and representatives of the
aiian Tuna Boat Owners Association and the
aiian Tuna Packers, Ltd.

CULTURE METHODS

REARING FACILITIES

Plant

ree redwood raceway-type tanks, each 5 feet
by 20 feet long and 3 feet deep, with a ca-
y of 1,400 gallons, were constructed on the
nds of the laboratory in October 1956 (fig.
The floors sloped downward toward the out-
end of the tank at the rate of 1 inch for each
eet of length. The outflow, located in one
er of the tank, consisted of a removable stand-
that slipped into a hole in the floor of the
and connected with a gate valve and drain-
on the outside. Baffle boards and a brass
n enclosed a triangular area occupied by the
dpipe. The baffle boards were raised about



FIGURE 1.—A redwood raceway tank at the pilot plant.

2 inches above the floor. Thus, the outflowing water was drawn from the floor of the tank and aided in removing detritus from the tanks. The brass screen prevented the fry from being carried out through the drain. The inflow, situated on the opposite end of the tank, was a faucet from which fresh water from the Honolulu water supply was dripped into the tank at the rate of one-half to 1 gallon a minute. The tanks were given a coat of aluminum paint before being used.

Initially, these three tanks were used as brood or spawning tanks. With the onset of fry production in December 1956, it was necessary to convert one of the tanks to a fry-rearing tank. Continued fry production created a need for more rearing space. In June 1957, a fourth redwood raceway-type tank, 30 inches wide by 30 feet long and 30 inches deep, with a capacity of about 1,250 gallons, was constructed adjacent to the other tanks. Screens of fine-meshed Monel stretched over square wooden frames were used to partition the tank into six approximately equal compartments. Each compartment had a siphon-type drain of plastic tubing. A standpipe drain was placed at one end of the tank in the event that the

siphons clogged or failed. Each compartment was served by a fresh-water tap.

In June 1957 we acquired a number of surplus assault boats from the U.S. Army, four of which were installed at the laboratory and used as brood and fry-rearing tanks. These undecked plywood boats measured approximately 4 by 12 feet on the bottom and each had a capacity of about 840 gallons. Although of very light construction, they were fairly watertight for more than a year. Water flowed in through a hose attached to the stern; the drain consisted of a plastic siphon attached to the bow. Several 1-inch holes were drilled in one side of the square bow just above the water line for controlled overflow if the siphon failed. Figure 2 shows an assault boat converted into a fish-holding tank, while figure 3 illustrates the plan of the pilot plant.

A filter system, consisting of a sand filter box and a pump, was installed experimentally on tank 2. It soon became apparent that the filter box was not adequate and that beach sand was inappropriate as a filtering medium. Cleaning and backflushing of the filter was necessary two or three times a week, requiring considerable time and effort. The sand was eventually replaced with several layers of fine-meshed Monel screen, which was not a very effective filter but did remove large amounts of fecal matter and other detritus. The turbulence and the splash on the surface caused by the water as it was returned to the tank under pressure also increased the oxygen concentration.



FIGURE 2.—An assault boat converted into a fish-holding tank, Kewalo plant.



FIGURE 3.—Plan of the tilapia pilot plant.

Other minor modifications in the pilot plant included installation of an aeration system and floodlights on tank 3. The aeration system consisted of an air compressor, a rubber air hose, and a pipe (drilled with holes) that ran crosswise of the floor in the center of the tank. Air was pumped through this pipe and slowly bubbled through the water in the tank.

Two 150-watt projector floodlights were installed on tank 3, one at each end, approximately 5 feet above the surface of the water. It was hoped, by day-and-night illumination, to increase the algal content of the tank, which was very low, and also possibly increase the production of young. No changes were detected, however, and the floodlights were removed after 3 months.

Kewalo Plant

In July 1958, the redwood tanks (three brood tanks and one fry tank) at the pilot plant were dismantled and reassembled at the Kewalo Basin docksite. A filter system (fig. 4), consisting of a sand filter box 24 inches wide by 26 inches long and 18 inches deep and a pump, was attached to each of the three brood tanks. The fry tank was modified by increasing the width 10 inches and by partitioning it with plywood separators (instead of screens) into six compartments. Essentially, each compartment was a separate tank with its own drain and tap. A filter box, 30 inches on the sides and 18 inches deep, and a pump were installed to filter and to recirculate the water.

The four assault-boat tanks at the pilot plant, after being in use for about a year, were not worth salvaging. Thirteen assault boats were removed from storage and converted into 12 brood tanks and 1 filter tank at the Kewalo plant. Drain water from the tanks was carried down a flume to the sand-filter tank and pumped back to each tank. All filter boxes contained a bottom layer of crushed rock and a top layer of coarse black sand (volcanic cinders), which was found to be much more effective than the fine beach sand used initially.



FIGURE 4.—Filter and pump on a raceway tank.

The general arrangement of the assault-boat tanks and the redwood tanks is shown in figure 5.

STOCKING THE BROOD TANKS

One of the first problems to be considered in the operation of the pilot plant was what sex ratio should be used when stocking the tanks. Chen (1953: p. 6), working on tilapia in Taiwan, stated that the proper sex ratio for propagation purposes is one male to a female. Other investigators, however, reported that in mouth brooders, which group includes *T. mossambica*, the female visits the spawning grounds only briefly to extrude her ova and collect the fertilized eggs, and then moves away or often is chased away by the male. The male remains on the spawning ground to guard the nest and immediately begins to court other females. He is, thus, available for and presumably capable of fertilizing ova from a succession of ripe females (Baerends and Baerends-Van Roon, 1950; Lowe, 1955). Lowe (p. 48), with respect to the mouth brooders, concluded that as male fish can continue fertilizing over a long period, the number of eggs ferti-



FIGURE 5.—Tilapia tanks at the Kewalo plant after a heavy rain.

619359 O—62——2

lized appears to be determined more by the number of ripe females than by the number of males.

Taking advantage of this behavior to realize a maximum production of young with a minimum of brood stock, a ratio of 2 ♀ : 1 ♂ was tried initially, with results that were considered to be successful. A later experiment at the pilot plant using a ratio of 5 ♀ : 1 ♂ yielded less-successful results, as will be described later.

Another important consideration was the density of the brood stock or carrying capacity of the brood tanks. Originally, it was decided to try a total of 48 fish with about 1.9 square feet per individual in one tank, and 96 fish or approximately 0.9 square foot per individual in the other two tanks, each with a sex ratio of 2 ♀ : 1 ♂ (table 1).

TABLE 1.—*Number of adults of each sex and space allowance per male and per individual, in brood tanks at the pilot plant*

Tank No.	Number of males	Number of females	Bottom area (sq. ft.) per—		Volume of water per individual (cu. ft.)
			Male	Individual	
1	32	64	2.8	0.9	1.9
2	32	64	2.8	.9	1.9
3	16	32	5.6	1.9	3.8

On October 12, 1956, the three tanks at the pilot plant were stocked with adult fish averaging 20 cm. (8 in.) in length and 150 g. (5.3 oz.) in weight. These fish were supplied by Hawaiian Tuna Packers, Ltd., and obtained from Ewa plantation pond No. 6. The initial mortality among the brood stock was very low, amounting to only three males and three females the first 15 days after stocking. All casualties were replaced. The exact number of adult fish in each of the tanks varied during the course of the test, however, owing to unobserved mortalities, vandalism, and the recruitment of juveniles that escaped dipnetting and grew to adult size in the brood tanks.

The stocking of the Kewalo plant followed an experimental design and will be discussed under factors affecting reproduction, page 37. Stock for the Kewalo plant was also obtained from Ewa pond No. 6. The males averaged 142 g. (5 oz.) and the females about 113 g. (4 oz.) in weight. No length measurements were made.

FEEDING

Many investigators have reported on the feeding habits of the various species of tilapia. Generally, *T. mossambica* is considered to be omnivorous (Schuster, 1952; Chen, 1953; Atz, 1954; Panikkar and Tampi, 1954; Brock and Takata, 1955; Van Pel, 1955). Vaas and Hofstede (1952: p. 35) stated that tilapia is herbivorous, but will feed on planktonic Crustacea "if such kind of food is more plentiful than vegetable food" and will show a preference for vegetable food when a mixture of the two is present.

Feeding of the brood stock at the pilot plant was started immediately after stocking was completed. Various types of commercial feed, such as rice bran (powdered), millrun (powdered), chicken starter mash (powdered and granules), alfalfa pellets (9/32 in. in diameter), pelletized rabbit feed (5/32 in. in diameter), and a pelletized pond-fish feed (5/32 in. in diameter), were tried to determine which were most acceptable to the fish. With a daily feeding rate of about 2 percent of the fish weight, we observed that finely divided, unpelletized feed, such as rice bran, millrun, and chicken mash, was not efficiently utilized because of the small particle size. The leftover feed contributed to fouling of the tanks. The alfalfa pellets and rabbit feed were also found to be undesirable because of their high content of indigestible fiber, which collected on the bottom of the tanks and also caused fouling.

Early observations on the feeding habits of the newly emerged fry indicated that they did not respond to supplementary feed until about 2 weeks after they were placed in the fry tank. The fry grade of pondfish feed (granules) was further ground to a flourlike consistency to accommodate the very young. The larger fry and juveniles reared at the pilot plant were fed pondfish feed in the crumble grade, which was slightly larger than the fry-grade granules.

Except in feeding experiments, the brood stock at the Kewalo plant was fed almost exclusively on a prepared trout feed (developer grade, about 1/4 in. in diameter), which in a smaller particle size was also fed to the fry (starter grade, powdered; fry grade, granules) and juveniles (small fingerling grade, crumbles). Table 2 gives the composition, supplied by the manufacturer, of the various feeds that were used.

E 2.—*Guaranteed analyses (percent) of ingredients in feeds used at the pilot plant and the Kewalo plant*

Feed	Protein [1]	Fat [1]	Fiber [2]	Ash [2]	Added minerals [2]	Nitrogen-free extract [1]	Moisture [2]
an	9.0						
a mash	20.0	4.0	4.5	7.5			
pellets	15.0	2.0	28.0	12.0		35.0	
h feed	30.0	4.5	6.0			28.0	
feed:							
veloper	25.0	4.0	3.5			44.0	
rter, fry, and mall fingerling	40.0	2.5	5.5	9.0		44.0	12.0
white middlings	13.5	3.0	4.0	5.0			13.0
	12.0	3.0	10.0	6.0			14.0
feed	16.0	2.5	21.0	10.0	3.0		

less than.
more than.

ne brood stock at both plants was fed once ay, usually at midday. There were periods ng the operation of both plants when the ts did not feed readily, and during these s smaller portions were supplied to the fish. apparent lack of interest in feeding is prob- associated with the mouth-brooding habit of female.

he amounts of the various kinds of feed that supplied to the adults and young during op- on of the pilot plant and the Kewalo plant given in tables 3 and 4. The fry were usually twice a day during weekdays, once in the ning and once just after midday, and once a

LE 3.—*Amount (in pounds) of the feeds used at the pilot plant*

Month	Rice bran	Chicken mash	Pondfish feed		Alfalfa		Rabbit feed
			Pellets	Crumbles	Pellets	Meal	
tober	2.5	2.5	25.0				
vember		8.8	50.8				
cember	22.0	16.0					
uary	23.3		11.0	3.5			
bruary			26.0	8.9			
arch			31.0	11.6			
ril			30.0	12.2			
ay			31.0	15.0			
ne			31.5	18.9			
ly			30.0	19.6			
gust		8.0	30.0	13.1			
ptember		15.2	30.0	14.8			
tober		14.0	31.5	21.5	1.0	0.8	
vember			36.8	14.0	7.2	7.0	
cember			46.0	11.4	7.8	3.6	
nuary			50.0	0.1	0.5		
bruary			38.5	0.1			
arch			42.6	4.8			
ril			40.4	6.0			
ay			1.4	3.5			44.2
ne				2.3			45.0
ly				1.2			25.0
er of pounds	47.8	64.5	613.5	182.5	16.5	11.4	114.2
ge cost per nd	$0.04	$0.05	$0.17	$0.27	$0.04	$0.04	$0.06

TABLE 4.—*Amount (in pounds) of the feeds used at the Kewalo plant*

Month	Trout feed		Rabbit feed	Mill-run	Wheat white middlings
	Developer	Fry and small fingerling			
1958:					
August	57.1		7.0	7.0	
September	111.6	0.2	14.8	14.8	
October	107.6	1.6	14.0	14.0	
November	93.1	2.5	13.0	13.0	
December		1.5			
1959:					
January	40.5	1.7			
February	42.0	1.7			
March	44.2	1.7	2.2		
April	22.5	5.2	22.5		
May	46.5	9.7			0.4
June	45.0	20.8			1.6
July	51.2	21.2			5.3
August	68.5	22.4			3.1
September	22.0	29.5			
Number of pounds	751.8	119.7	73.5	48.8	10.4
Average cost per pound	$0.13	$0.13	$0.06	$0.04	$0.05

day on weekends. The amount of feed given to the young varied with the number and size of fry and juveniles.

FRY PRODUCTION

T. mossambica reportedly first spawns at the age of 2 to 3 months and at a length of 8 to 9 centimeters. The frequency of spawning varies considerably, depending on environmental factors, and ranges from 6 to 16 times a year (Chen, 1953; Panikkar and Tampi, 1954; Chimits, 1955). Chen reported that a spawning fish of about 8 cm. in length produces from 100 to 150 ova at each spawning, although at the first spawning it may produce less than 100 ova. He stated further that the number of ova spawned increases with successive spawnings, so that a fish more than 6 months of age may produce in excess of 1,000 ova per spawning.

The developmental period of the ova is likewise variable but, generally, the ova hatch after 2 to 5 days and the young are carried in the mouth of the female for another 5 to 8 days before they are released (Chen, 1953; Panikkar and Tampi, 1954; Chimits, 1955).

From the time of the initial stocking at the pilot plant, careful daily observations were made on each tank to determine if young were being produced. As no signs of young fish were seen for about 6 weeks, the three tanks were partially drained and cleaned on November 28–29, 1956. Before the water level was restored in each tank, the detritus on the bottom of the tank was ex-

amined for signs of ova and young. The females were also examined to see if ova or young were being carried in the mouth. It was noted at this time that all the brood stock appeared in excellent condition but there were no signs of spawning.

On December 5, 1956, one-half cubic yard of white beach sand was placed in two of the brood tanks (tanks 1 and 3), covering the bottom to a depth of about 3 inches. It was our original intention to determine if the tilapia would spawn on the bare floor of the tanks, which seemed probable in view of Chen's (1953: p. 7) observation that tilapia were seen spawning successfully in a garden pond with a concrete bottom.

Good evidence of excavating and nest-building was noted the next morning following placing of the sand, and the nests continued to increase in number during the next few days until they occupied at least two-thirds of the sandy bottom. Two weeks after the sand was placed in the tanks, the first young were noticed on the surface of tank 1. The young were removed and subsequently placed in tank 2, which was drained and converted into a fry tank. Six days later, the fish in tank 3 started to produce young.

During the draining of tank 2 in preparation for conversion into a fry tank, one large male was observed carrying six yolk-sac fry in its mouth cavity, although in this species the female is supposed to brood the young. This behavior was also observed by Vaas and Hofstede (1952), who reported that the male incubated the ova in exceptional cases. Further evidence of spawning was found in tank 2, where many ova and yolk-sac fry were seen widely scattered on the tank floor. It was our supposition that the adults had become excited as the water level dropped and ejected the ova and fry.

At the Kewalo plant, where all the brood tanks were supplied with sand, fry production started 11 days after the tanks were stocked. Further data on fry production at the Kewalo plant will be presented later in this report, together with the results of the various experiments.

FRY COLLECTION

Newly hatched fry of *T. mossambica* measure 5 millimeters in length, 5.8 mm. on the second day, and 8.0 mm. at the end of the fifth day. On about the fifth day, they begin to spend less time in the mouth of the female or leave it altogether and swim about in a tight school near the surface of the water, feeding on tiny food particles (Panikkar and Tampi, 1954). This behavior of the fry made their capture by dipnetting a relatively simple process. Another behavior pattern that became evident to us through daily observation was the tendency for the fry to congregate along the walls of the tank, especially in the corners and, at times, directly under the inflowing water.

At both plants, the young emerging each day were captured with a fine-meshed dipnet and counted as they were released into the fry tank. Although our daily netting effort varied somewhat in efficiency, as indicated by the different-sized young netted, the method proved to be quite effective as evidenced by the few juveniles that were removed from the tanks when they were drained.

Early in the operation of the pilot plant, the displacement and weight methods for assessing the daily production of young were considered, but both had major drawbacks for enumerating the very small tilapia fry. We concluded that only by an actual count could we obtain the accuracy desired.

In August 1957, a shelf-collection method of capturing young was investigated at the pilot plant. This method was originally the idea of biologists of the Hawaii Division of Fish and Game who observed that tilapia fry tended to congregate in shallow water near the edge of the ponds. Consequently, it was hypothesized that if the fry had shallow water available to them along the walls of the brood tank, perhaps their capture would be simplified.

A redwood shelf, running the length of the inside wall just below the waterline, was installed in tank 1. The water level in the tank was maintained so that the outer edge or lip of the shelf was ordinarily about one-half inch below the surface. The water over the shelf could be drained through a hole in the wall of the tank and the young fish caught in a net.

Comparison of the number of fry collected from the shelf with that collected elsewhere in the tank by dipnetting indicated that the shelf was effective in the removal of only about 25 percent of the fry that emerged daily. Further, many of the fry congregated under the shelf, rather than over it.

ew of the results that were obtained, the shelf tion method was abandoned.

FRY REARING

fry production increased, it became a serious em to provide sufficient space for the young Initially, the fry were placed in one large nk. After a few weeks, cannibalism became spread: the juveniles readily devoured the collected fry when they were transferred fry tank. As a remedy, removable frames ed with fine-meshed Monel screen were in- d in the tank dividing it into three compart- s. The fry and juveniles could then be segre- by age and size.

th the construction of a new fry tank with mpartments and the acquisition of four as- boat tanks at the pilot plant, additional for rearing the young was available. The dure became standard to place the fry in the nk for about 4 to 5 weeks, after which time were transferred to assault-boat tanks.

en fry were removed from the brood tanks, usually ranged in size from 7.8 to 13.6 mm., the average about 10.8 mm. Of a total of 154 anging from 7.8 to 10.3 mm., about 26 percent ed remnants of the yolk sac. The newly col- fry, as mentioned earlier, generally paid lit- no attention to the prepared feed when first d it and only took it after about 2 weeks in y tank.

as and Hofstede (1952) observed that young ia fed on diatoms, unicellular green algae, Crustacea, and periphyton. Varying num- of these organisms were present in the tanks undoubtedly constituted a major portion of iet of the fry during their first few weeks e after absorption of the yolk sac. The feces e young fry were usually bright green, in- ing that algae were a major constituent of diet.

e necessity of utilizing all fry-rearing space able during periods of heavy fry production ionally forced us to overcrowd the fry tank frequently resulted in an outbreak of disease. terion for determining when an overcrowded ition existed was difficult to formulate, but gh experience we arrived at what we con- ed an optimum stocking density. The gen- plan was to stock the fry-tank compartments with approximately 200 fry per square foot of surface area and crop each compartment at frequent intervals, removing the larger, faster-growing individuals; i.e., fish that were 20 mm. (0.75 in.) or larger. In this manner, cannibalism and disease were kept to a minimum. Also, through the necessity of occasionally overcrowding the juveniles in the assault-boat tanks, we learned that they were much more tolerant to crowding than were the fry and also that they were afflicted less frequently with ectoparasites.

The most critical period for the fry appears to be the first 4 to 5 weeks of life, for it is in this period that the fry are most susceptible to infectious diseases and ectoparasitic infestation. Proper sanitary conditions in the tanks and adherence to an optimum stocking density for a given area seem to be the two most important factors determining survival and subsequent health of the fry.

LENGTH-WEIGHT RELATION OF YOUNG

During the operation of both plants, it was frequently necessary to estimate the size and quantity of young fish on hand. In order to have a convenient means of converting length into weight and vice versa, the length-weight relation for tilapia 17 to 73 mm. in length was determined from body measurements of 109 fish. The logarithmic formula for the expression of this relationship is

$$\log W = 3.088 \log L - 4.8935$$

where W is the weight in grams and L is the length in millimeters. A curve demonstrating the length-weight relation is shown in figure 6.

WATER-QUALITY DETERMINATIONS

Some chemical determinations were made routinely once each week. Only oxygen measurements were made at the pilot plant; but at the Kewalo plant, additional properties, such as free carbon dioxide, bicarbonates, normal carbonates, and hydrogen-ion concentration were also measured weekly in selected tanks.

Oxygen Content

Determinations of dissolved oxygen in the brood and fry tanks were made by the modified Winkler method. Analyses were made once a week at



FIGURE 6.—Length-weight relation for tilapia 17 to 73 mm. in length.

about the same hour each time to obtain a general record of the variation in oxygen content of the water (appendix tables 1, 3, 4, and 5). In a 24-hour series (with sampling at hourly intervals) obtained at the pilot plant November 12–13, 1957, we found a marked diurnal change in the concentration of oxygen in the tanks, the minimum concentration occurring at about daybreak and the maximum concentration at about midafternoon (fig. 7; appendix table 2). The maximum concentration was certainly the result of photosynthesis by the algae in the tanks, and the minimum was caused by respiration of both algae and fish. Water temperatures in the tanks showed a similar diurnal variation, with the occurrence of maximum and minimum temperatures corresponding very closely to the maximum and minimum concentrations of oxygen.



FIGURE 7.—Diurnal variation in oxygen concentration and temperature in tanks 1 and 2 at the pilot plant.

Vaas and Hofstede (1952) stated that *T. mossambica* has a high metabolic rate compared with carp, and that oxygen is consumed and carbon dioxide liberated in large quantities within a short time by the species. They also found that when oxygen tension is low, especially during the morning, the fish concentrate at the surface of the water suspended in a diagonal position, sucking in the well-aerated water of the surface layer with wide-open mouths.

It is suspected that some of the mortalities among the adults at both plants were associated with an insufficient amount of oxygen. In tank 3 at the pilot plant, deaths occurred periodically for about 2 months in the summer of 1958. During this period, the oxygen minima occurring in the early morning were consistently low, averaging only 0.38 ml./l. Of the 10 adults that died during this period, 9 were large males averaging 29 cm., and the single female was 23 cm., perhaps indicating the greater susceptibility of the larger tilapia to low oxygen concentration.

Since our purpose in sampling oxygen was primarily to monitor environmental suitability, we have not attempted to relate the data to fry production, except in the heating experiment, where low oxygen concentrations were believed to be associated with the poor fry production. From the data it appears that, in most instances, the minimum or near-minimum oxygen concentration in the sampled tanks was sufficient to sustain the tilapia.

Hydrogen-Ion Concentration

Determination of hydrogen-ion concentration was made by the colorimetric method at the time the oxygen samples were drawn. The pH values of the tanks that were sampled (appendix tables 6–8) ranged from 7.3 to values exceeding 8.8 (the color standard used at first could measure pH only to 8.8). It was expected that the pH in our tanks would remain on the alkaline side, since city water (pH range, 7.9 to 8.3) was used and, with the exception of the fry tank, the tanks contained a 3- to 4-inch layer of calcareous beach sand.

e hydrogen-ion concentration and its signifi- to aquatic organisms has been relegated for time to a minor position by many investiga- Welch, 1935; Odum, 1959). It may possibly imiting factor to some organisms, however.

Carbon Dioxide

alysis of the amount of free carbon dioxide e tanks was started at the Kewalo plant in uary 1959. The samples were drawn im- ately after those for the oxygen determina- nad been drawn and fixed. The amount of carbon dioxide present was approximated by ion of a 100-ml. sample to the phenolphtha- ndpoint with 0.02 N sodium hydroxide.

lch (1935: p. 175) stated that carbon dioxide of the most important substances in the life ganisms, but that it should be present only r suitable circumstances and in proper nts. He stated further that a small amount rbon dioxide appears to be essential for ic animals. Doudoroff (1957) regarded free n dioxide concentrations between 100 and .p.m. as fatal to moderately susceptible fresh- fishes; also, that exposure to concentrations en 50 and 100 p.p.m. causes immediate dis- and may be lethal if the exposure is pro- d. He noted that even in polluted waters carbon dioxide concentrations rarely exceed p.m.

roughout the period of sampling at the lo plant, the free carbon dioxide concen- n (appendix tables 9 and 10) was never d to be in excess of 16.2 p.p.m. No attempts made to determine a relation between carbon de concentrations and fry production. Our ne observations were made primarily to de- excessive amounts of free carbon dioxide in rood and fry tanks.

nity

emical analyses of the water in the tanks at Kewalo plant included determinations of total bonate and carbonate alkalinity. A 100-ml. le was titrated with 0.02 N sulfuric acid st the phenolphthalein and methyl orange oints.

kalinity directly influences the biological pro- ivity of a body of water. The carbonates and bonates, which are in close chemical com- ion with carbon dioxide, are utilized by algae (Welch, 1935), and also act as buffers by keeping the hydrogen-ion concentration close to the neutral point (Odum, 1959).

Our alkalinity determinations (appendix tables 8 and 10) were made primarily to gain a general knowledge of the type of water present in the tanks, as soft water has a smaller supply of these ions and, therefore, is less productive.

MORTALITIES

Among the Adults

Observed mortalities among the brood stock amounted to 31 males and 11 females at the pilot plant and 55 males and 56 females at the Kewalo plant. The dead fish were carefully examined and deaths were usually attributable to one of the following factors: Rough handling, disease, asphyxiation and, possibly, hydrogen sulfide poisoning.

While it might have been possible to reduce mortalities by using more care in handling fish and by proper treatment of diseased fish, it was not always possible to prevent mortalities caused by asphyxiation, since many factors contributed to the oxygen concentration in the tanks.

The heaviest mortality to occur in a single day among the adults was experienced at the Kewalo plant. A total of 7 males and 29 females was found dead in the two brood tanks containing brackish water (salinity-spawning experiment) and the deaths were believed to have been caused by either asphyxiation or hydrogen sulfide. Faint odors of hydrogen sulfide gas were detected in the brackish-water tanks for several days before the mortalities occurred, and, undoubtedly, this gas was one of the contributing factors, if not the determining factor in the deaths. The tanks were not drained and cleaned at the time hydrogen sulfide was first detected in the tanks, however, because the experiment was to be terminated within a few days.

Among the Young

Many factors contributed to the loss of young fish, chief of which was disease, with deaths from handling judged to be of secondary importance. At the pilot plant, the observed mortality in the fry tank amounted to 34,784 fish, while juvenile deaths totalled 4,523 fish. Although the total observed mortality among the young amounted to

15.5 percent of the 253,548 fish produced, the unobserved mortality (difference between net production and observed distribution and losses) was much higher, amounting to an estimated 42,900 fish or about 17 percent of the total production. The causes for these unobserved losses were difficult to assess, but presumably can be attributed to a variety of factors: vandals entering the plant and removing unknown quantities of fish; loss of fish through the drain; predation by dragonfly nymphs; and cannibalism. Davis (1946: p. 9) in reporting on "uncounted mortality" in trout hatcheries stated that this was due "either to improper construction of the raceways, so that many of the fish are able to escape; to the attacks of enemies, such as fish-eating birds; or to cannibalism."

At the Kewalo plant, observed mortalities among the young amounted to 44,600 fish or about 13 percent of the 347,700 fish produced.

DISEASE PREVENTION AND CONTROL

Prevention and control of fish diseases and infestation of parasites are important factors in the success of any type of fish-rearing program. Fish, like other animals, are subject to a wide variety of infectious diseases and parasites and seem particularly susceptible in an unnatural or artificial environment.

Several outbreaks of disease or parasitic infestation were observed among tilapia at both the pilot plant and the Kewalo plant. All dead fish were examined microscopically for signs of unnatural conditions, such as mucous film or irregular blotches on the body and unusual blisters or swelling. When sick fish were observed in the tanks, similar examinations were made on their external surfaces, gill region and, on occasion, the gastrointestinal tract. It was not always possible to distinguish between losses from diseases and from other causes, although in many instances of high mortality rates parasites were seen and identified to genus. Several exceptions occurred when the cause of high mortality rates among the fry could not be determined by isolation of any causative organism. By careful observation of symptoms, it was possible on a few occasions to restrict the probable cause of death to a virus infection. In general, the fry, juveniles, and adults were susceptible to infection in that order.

Trichodina spp.

Infestation by the ectoparastic trichodinids, considered one of the most highly specialized protozoans, was the most common malady among adult and young tilapia, with infestation along the dorsal fins, dorsal region of the caudal peduncle, and gill region being most prevalent. Tilapia with trichodiniasis were sluggish, showed loss of appetite, had a reddish tinge on the skin in the caudal-peduncle region, and, in some instances, in and around the region of the dorsal fins, they had white blotches accompanied by a fraying of these fins.

According to Davis (1953: p. 220), *Trichodina* is very easy to control. We used several recommended treatments such as salt (1.23 percent), acetic acid (1:500), formalin (1:4,000), pyridylmercuric acetate or PMA (2 p.p.m.), copper sulfate (0.5 p.p.m.), and potassium permanganate (3 p.p.m.). All of these reagents proved effective in controlling the disease; however, as more experience was gained, we found that potassium permanganate was the most suitable, since it was exhausted after a period of time and the treated tank did not need to be flushed, as was required with the other chemicals.

Chilodon spp.

Only a few outbreaks of disease were attributable to this protozoan, a common ectoparasite of warm-water fishes. Davis (1953) states that this organism may be very destructive to fish crowded in small holding tanks or ponds and has been known to cause serious losses among trout fingerlings.

On a number of occasions, both adult and young tilapia were found to be infested with this parasite. Areas infested were usually the dorsal and caudal fins and along the dorsal surface of the fish, especially near the base of the dorsal fins. Very frequently, trichodinids were also present.

Treatment to rid the fish of this parasite was usually with potassium permanganate or with PMA, although the former was used more extensively because of its ease of application.

Infectious Pancreatic Necrosis

Infectious pancreatic necrosis, until recently known as acute catarrhal enteritis (Lagler, 1956; Snieszko and Wolf, 1958), was the most serious

ion of young tilapia. Outbreaks of the dis- aused high mortality rates among fry about weeks old, soon after they had started sup- ntary feeding. Symptoms characteristic of isease were violent whirling or corkscrewing panied by rapid breathing. The afflicted fish ly exhibited a series of these whirling move- , then sank to the bottom of the tank and ed feeding. Cessation of feeding caused of the fry to have a "pinhead" appearance, is, a large head and shrunken body.

ese symptoms are similar to those described tomitiasis, commonly called whirling disease nhead condition (Lagler, 1956; Davis, 1953; zko and Wolf, 1958). Octomitiasis is caused e protozoan *Octomitus salmonis*, which oc- in the intestine either in the flagellated form, the condition is chronic, or in an intracel- stage, when the disease is acute. The etiology nfectious pancreatic necrosis, on the other , is still in doubt, although it has been re- d as probably caused by a virus (Lagler, Snieszko and Wolf, 1958).

of the symptoms noted here were observed e particular outbreak of disease at the pilot . Dissection and examination of the stomach nterior intestine of six afflicted fish revealed nly one fish had a protozoan in the intestine. f the others appeared normal internally. On assumption that this disease was probably nitiasis, we started immediate treatment with arsone (p-Ureidobenzene arsonic acid) at the of 1 gram per pound of food (Davis, 1953). mortality rate decreased appreciably in the few days following treatment and by the end e tenth day had been reduced to a low level. ough Carbarsone seemingly effected a cure, we ot certain that *Octomitus* was the causative nism, since the protozoan was not positively ified. It might possibly have been infectious reatic necrosis, or an acute infection of nitiasis caused by the intracellular stage of the llate, or a combination of the two. Snieszko Wolf (1958) state that many cases diagnosed tomitiasis are in reality infectious pancreatic sis. Careful microscopic examination is sary for correct diagnosis.

bsequent periodic outbreaks of infectious reatic necrosis were definitely identified by ination of the stomach and anterior intestine of diseased individuals. In most instances these organs were distended and filled with a colorless, opaque fluid, indicating a stoppage of bile flow. As there is no known effective therapy for this disease, the usual procedure was to treat the fish with potassium permanganate at a concentration of 3 p.p.m. to prevent secondary infection of the weakened fish with ectoparasites and to observe strict sanitation measures. In this way, we believe that most of the disease outbreaks were kept localized.

Mortality rates among the fry were usually highest during the first week after an outbreak and gradually subsided during the following 2 to 3 weeks. The most serious outbreak of disease occurred at the Kewalo plant soon after it was in operation. A succession of infections that spread among the newly emerged fry caused an estimated loss of about 80 percent of the 146,776 fry produced in a 3-month period. The disease was controlled after 10 weeks.

Prophylactic Measures

Despite knowledge that the density of fish is extremely important in relation to the outbreak and spread of disease, we tended to overcrowd our tanks on occasion. Since the amount of fry-rearing facilities was limited, it was impossible to avoid overcrowding during periods of heavy fry production unless we discarded some of the young fish. Our records indicate that several of the disease outbreaks were directly associated with periods of high production. Whenever an overcrowded condition existed, we made every effort to prevent disease outbreaks by increasing the rate of the inflowing water, by cropping the fry-tank compartments frequently, and by observing strict sanitation.

Effective prophylactic measures are probably of greater importance than control measures in successful fish culture. Potassium permanganate was periodically added to the water as a prophylactic measure and, when conditions permitted, tanks which held any diseased fish were thoroughly scrubbed with a brush, refilled with water, and copper sulfate or formalin was added in high concentration. The environment thus created was believed unfavorable to whatever ectoparasites may have remained in the tank after the scrubbing.

619359 O—62——3

FACTORS AFFECTING FRY PRODUCTION

In commercial bait-rearing operations, it is necessary to obtain maximum production and survival of young from a minimum-sized brood stock. Insofar as possible, optimum conditions of temperature, salinity, food, sex ratio, and brood-stock density are maintained. Some preliminary information was obtained at the pilot plant and more detailed information at the Kewalo plant on the importance of these factors.

TEMPERATURE AND SPAWNING

Fry production started in December 1956 at the pilot plant, and by mid-January 1957 it was apparent that the brood stock in tank 3 was not as productive as that in tank 1.

Environmental conditions in the two tanks differed in several respects. The water temperature in tank 3 averaged 1° to 2° F. cooler than in tank 1. This difference probably arose from the fact that tank 3 was shaded by trees and a storage shed most of the day, whereas tank 1 was situated in more open surroundings and received more hours of direct sunlight. In an attempt to eliminate the temperature difference, the water entering tank 3 was piped through a 100-foot length of black, three-fourths-inch, garden hose that was stretched across the roof of the storage shed. On sunny days, the temperature of the water flowing into tank 3 was raised as much as 5° to 10° F. and the temperature of the water in the tank to about the same level as in tank 1 (table 5).

A second major difference between the tanks was the consistently lower oxygen concentration in tank 3. This condition probably accounted for the dead yolk-sac fry that were frequently found in the detritus siphoned from the floor of the tank. Aeration brought about a significant increase in the concentration of oxygen in tank 3 (appendix table 1).

The pattern of water circulation was also different in the two tanks. The flow of water from inlet to outlet in tank 3 opposed the prevailing wind while that in tank 1 was in the direction of the prevailing wind. The resulting circulation pattern kept tank 1 relatively clean and the water usually green with algae, while tank 3 had much detritus and generally stagnant water. The color of the water in tank 3 varied from clear to light green to dark brown. Improvement in water circulation in tank 3, resulting from aeration and slight heating of the water, was sufficient to produce a significant increase in fry production during March 1957. Tables 6 and 7 give the production per female per month for these brood tanks (tank 2, which was later converted to a brood tank in August 1957, was similar in all respects to tank 1).

TABLE 5.—*Average minimum and maximum temperatures (° F.) in tanks 1 and 3 at the pilot plant*

Month	Tank 1		Tank 3	
	Average temperature		Average temperature	
	Minimum	Maximum	Minimum	Maximum
1957:				
January	70.8	75.6	70.1	75.5
February	69.8	75.2	68.6	75.2
March	71.3	78.0	69.8	78.2
April	71.3	78.0	71.2	78.9
May	72.8	81.3	73.2	81.3
June	74.7	82.3	75.6	82.5
July	74.9	83.3	76.5	82.2
August	75.7	82.6	75.6	81.1
September	[1]	[1]	76.0	81.9
October	[1]	[1]	75.2	80.3
November	72.8	77.0	74.2	78.2
December	70.3	74.5	70.7	74.4
1958:				
January	69.9	74.9	70.2	74.0
February	70.6	76.7	70.7	75.7
March	70.8	77.3	70.8	76.2
April	72.7	79.6	71.6	78.1
May	73.7	80.1	72.8	77.8
June	75.6	82.9	73.8	79.5
July	75.4	82.6	73.9	79.2

[1] No data; thermograph out of order.

TABLE 6.—*Fry produced in tank 1, per female and month, at the pilot plant, December 1956–July 1958*

Month	Brood stock		Number of fry produced		Feed
	Males	Females	Total	Per female [1]	
1956: December	32	64	578	9.0	Chicken mash and rice bran.
1957:					
January	32	64	4,498	70.3	Rice bran.
February	32	64	2,107	32.9	Pondfish feed.
March	32	64	6,433	100.5	Do.
April	32	64	4,050	63.3	Do.
May	32	64	20,297	317.1	Do.
June	31	64	6,146	96.0	Do.
July	31	64	20,910	326.7	Do.
August	31	64	18,520	289.4	Chicken mash.
September	31	64	7,743	121.0	Do.
October	31	64	4,159	65.0	Do.
November	29	64	188	2.9	Alfalfa pellets and pondfish feed.
December	31	64	409	6.4	Do.
1958:					
January	19	59	0	0.0	Pondfish feed.
February	22	61	143	2.3	Do.
March	19	58	48	0.8	Do.
April	19	58	1,418	24.4	Do.
May	17	58	10,701	184.5	Rabbit pellets.
June	17	58	9,158	157.9	Do.
July	12	58	6,172	106.4	Do.

[1] Because of mortalities and transfer of fish, the number of females used to calculate the production per female is based on the number of females that were present in the tank for more than 2 weeks.

7.—*Fry produced in tank 3, per female and month, at the pilot plant, December 1956–July 1958*

nth	Brood stock		Number of fry produced		Feed
	Males	Females	Total	Per female [1]	
cember	16	32	69	2.2	Chicken mash and rice bran.
nary	55	93	0	.0	Rice bran and pondfish feed.
ruary	31	63	374	5.9	Pondfish feed.
rch	31	63	1,278	20.3	Do.
il	31	62	8,322	134.2	Do.
y	31	62	13,685	220.7	Do.
e	31	62	9,290	149.8	Do.
r	31	62	14,197	229.0	Do.
ust	31	62	9,327	150.4	Do.
tember	31	62	2,621	42.3	Do.
ober	31	62	1,769	28.5	Do.
ember	31	62	1,294	20.9	Do.
ember	31	62	274	4.4	Do.
nary	31	62	32	.5	Do.
ruary	30	61	147	2.4	Do.
rch	29	61	213	3.5	Do.
il	29	61	566	9.3	Do.
y	29	61	3,205	52.5	Rabbit pellets.
e	28	61	78	1.3	Do.
r	20	60	92	1.5	Do.

[1] use of mortalities and transfer of fish, the number of females used to e the production per female is based on the number of females that esent in the tank for more than 2 weeks.

second experiment in which the effect of tem- ure on production of young was examined onducted at the Kewalo plant from Janu- o August 1959.

r tilapia to be most useful as a supplementary ack bait, there must be a stock of bait-size n hand in May or June, at the beginning of main fishing season in Hawaiian waters. chieve this, heavy fry production must be r way by late winter. Brock and Takata 5: p. 24) reported that tilapia spawn through- the year in Hawaiian waters, but that the ning is less intense during the winter months. equently, an experiment was conducted at Kewalo plant to determine if raising water eratures would induce tilapia to spawn at a rate during the winter months. Three red- l tanks (tanks 13, 14, and 15) were arranged llows for the experiment:

Tank 13 was not modified in any way and ed as the control.

The water in tank 14 was artificially heated a 60-foot, lead-sheathed heating cable rated A–115V, that produced 400 watts, or 6.7 watts oot. A thermostat with a capillary tube was ed in the tank to control the temperature. A made of sisal-glaze, a clear, longlasting ic, was placed over the tank (fig. 8) to pre- excessive heat loss, especially at night.



FIGURE 8.—Plastic cover over artificially heated tank 14.

3. The water in tank 15 was also artificially heated with the same type of heating cable used in tank 14, but the tank was not covered to prevent heat loss.

Each tank was stocked with 32 males and 64 females and fed trout feed. Emerging fry were collected and counted daily. The daily variation in water temperature was recorded by thermographs and minimum and maximum thermometers.

The production per female per month and the average and range of minimum and maximum temperatures for each of the three tanks are recorded in table 8 and shown graphically in figure 9. In January, tank 14, which was modified with heating cable and cover, had relatively better production than the other two tanks. In February, artificial heating was started in tank 15, and resulted in a marked increase in production comparable to that in tank 14. Production was still low in the control tank. In March, with rising air temperatures the water warmed in all three tanks and production increased in all; however, the increase in the slightly warmed tank 15 greatly exceeded that in the other tanks. Temperatures remained about the same in April, but production dropped, particularly in tanks 14 and 15. With higher temperatures in May, the control tank maintained its slight lead over tank 15, and during the last 3 months of the experiment, it outproduced the two artificially heated tanks by a significant margin. Over the course of the experiment, total fry production in tank 13 (control) was about twice that in the other two tanks.



FIGURE 9.—Production per female per month in the heated tanks and in the control tank, and average minimum and maximum water temperatures in the tanks.

Analysis of the data indicates that although some increase in spawning was induced during the winter months by raising the water temperature, the increase in production was not great. In addition, only a slight rise in water temperature apparently produced the same results as a marked increase in temperature. The results also indicate that prolonged or constant high temperatures may be detrimental to spawning. Innes (1951) pointed out that at constant high temperatures the oxygen content of the water becomes diminished and this seems to have a weakening effect on fish. Doudoroff (1957: p. 415) stated—

> that persistent nonlethal deficiency of dissolved oxygen undoubtedly can adversely influence the activities of fishes and have serious detrimental effects on fish populations in their natural environments.

The oxygen record (appendix table 4) discloses that throughout the period of the experiment, tank 14 had generally lower concentrations of oxygen, which may account for the decrease in fry production during the summer months.

Although tanks 13 and 15 had similar temperatures, fry production in these two tanks differed significantly for the months of June to August. While it is true that tank 15 was heated artificially (thermostat set at 80° F.), much of the heat was lost through convection. Thus, tank 15 remained only slightly warmer than the control tank. The average temperatures in both tanks fell within the optimum temperature range for propagation, which is from 20° to 35° C. (68° to 95° F.) according to Chen (1953), while the weekly oxygen determinations showed very little difference between the two tanks. We are unable to advance a satisfactory explanation for the poor fry production in tank 15.

TABLE 8.—*Summary: Fry production and temperatures of brood tanks used in the heating experiment, January–August, 1959*

[Temperature ° F.]

Month	Number of fry produced		Average temperature		Temperature range	
	Total	Per female	Minimum	Maximum	Minimum	Maximum
Tank 13 (control):						
January	2,967	46.4	71.4	77.4	63.0	83.4
February	2,492	38.9	67.9	74.8	64.2	78.5
March	5,032	78.6	70.6	78.2	67.7	81.9
April	4,739	74.0	72.1	80.1	67.1	84.6
May	7,365	115.1	73.5	81.8	70.1	86.4
June	14,456	225.9	75.0	83.6	72.6	86.2
July	19,319	301.8	77.0	85.1	74.3	90.4
August	5,010	78.3	77.3	85.4	72.3	90.3
Total	61,380					
Tank 14 (with heating cable and cover):						
January	4,064	63.5	77.3	81.4	72.1	88.3
February	4,448	69.5	77.2	81.8	74.8	84.6
March	5,922	92.5	80.4	85.9	78.0	88.0
April	992	15.5	79.8	85.2	76.0	90.7
May	4,804	75.1	81.2	87.2	76.8	90.2
June	4,935	77.1	82.5	88.6	81.0	90.6
July	2,376	37.1	83.5	89.4	79.0	90.9
August	0	0.0	84.1	89.5	79.8	90.9
Total	27,541					
Tank 15 (with heating cable):						
January	3,046	47.6				
February	4,424	69.1	69.6	76.0	65.0	78.0
March	11,166	174.5	72.1	79.6	69.0	83.0
April	4,660	72.8	73.6	81.0	69.0	85.0
May	7,269	113.6	74.8	82.6	72.0	87.0
June	4,905	76.6	75.7	83.7	73.6	85.4
July	1,555	24.3	77.3	85.4	74.0	89.9
August	822	12.8	77.9	85.6	72.8	89.4
Total	37,847					

SEX RATIO AND BROOD-STOCK DENSITY

ratio of 2 ♀ : 1 ♂ was used initially at the plant and judged to yield satisfactory re-. The best production resulting from this ratio was realized during July 1957 at the plant, when production in tank 1 amounted),910 fry or 327 fry per female (table 6). A nd grouping of 5 ♀ : 1 ♂ (total stock, 72) was tried in tank 2 from August to November, . The production per female per month is n in table 9. The best production for that od and grouping occurred in August, when production amounted to 2,532, or 42 fry per ale.

LE 9.—*Production of fry per female per month in tank 2 at the pilot plant, August 1957–July 1958*

Month	Brood stock		Number of fry produced		Feed
	Males	Females	Total	Per female [1]	
ugust	12	60	2,532	42.2	Pond-fish feed.
ptember	12	60	2,383	39.7	Do.
tober	12	60	1,535	25.6	Do.
vember	12	60	0	0.0	Do.
ecember	16	56	107	1.9	Do.
nuary	16	56	3	0.1	Do
bruary	16	56	2,891	51.6	Do.
arch	16	56	7,691	137.3	Do.
pril	16	56	6,660	118.9	Do.
ay	31	72	11,627	161.5	Rabbit pellets.
ne	31	72	19,826	275.4	Do.
y	29	72	7,781	108.1	Do.

cause of mortalities and transfer of fish, the number of females used ulate the production per female is based on the number of females that resent in the tank for more than 2 weeks.

more detailed experiment designed to deter-e the ideal sex ratio for maximal yield of was conducted at the Kewalo plant from Sep-ber to November 1958. The effect of brood-k density on spawning was simultaneously stigated in the same experiment.

he 12 assault boats mentioned earlier were ked with various sex ratios and concentrations ish. The design of this partially confounded orial experiment is shown in table 10. The d stock was fed dry trout feed at the rate of ercent of its weight daily. It was assumed any differences in temperature or oxygen con-rations which might occur among the tanks ld not bias the results.

TABLE 10.—*Sex ratios and concentrations of tilapia used to stock the 12 assault-boat tanks, September–November 1958*

Sex ratio (♀:♂)	Sex ratio in concentration of							
	30 fish		50 fish		70 fish		90 fish	
	♀	♂	♀	♂	♀	♂	♀	♂
2:1	20	10	33	17	47	23		
3:1	23	7	38	12			68	22
4:1	24	6			56	14	72	18
6:1			43	7	60	10	77	13

The experiment was terminated after 13 weeks. An analysis of variance of the data (table 11) indicated significant differences ($F=5.73$, $P < 0.01$) between fry production with respect to the sex ratios used in the experiment. (A probability level of 5 percent is considered the maximum value for a conclusion of significance in this report.) The most productive ratio was 3 ♀ : 1 ♂ (tanks 4 and 5). Tanks 1 and 2 with a ratio of 2 ♀ : 1 ♂ were almost equally high in production for the first 2 months of the experiment (fig. 10).



FIGURE 10.—Production per female in relation to sex ratios and concentrations of brood stock.

The relation between total production per female and bottom area (square feet) per male is shown in figure 11, while the total production per female in relation to bottom area per individual is shown in figure 12. From table 11 and



FIGURE 11.—Total production per female in relation to bottom area (sq. ft.) per male. (Total stock in parentheses.)

figures 10 to 12, it may be seen that the tanks with 50 fish or less (except tank 10) had a much better production than those with more, while an allowance of 4 square feet of bottom area per male and 1 square foot per individual gave the highest production per female (see tank 5, table 11).

The analysis of variance showed that the differences in fry production with respect to the concentrations, 30, 50, 70, and 90 fish, used in the experiment were significant ($F = 11.44$, $P < 0.01$). There was also a significant interaction between sex ratios and brood-stock density, indicating that the production resulting from any specific ratio did not vary in a uniform manner with respect to availability of space.

DIET AND REPRODUCTION

Early attempts to assess the qualities of different types of feed in relation to fry production at the pilot plant proved inconclusive, owing to dissimilar conditions in the brood tanks (tanks 1 and 3). However, we were able to observe the general acceptability of the five types of feed that were used.

Finely ground feed, such as rice bran and chicken mash, was found to be unsuitable for the adults as they cannot strain small particles from the water. Much of the feed was wasted and



FIGURE 12.—Total production per female in relation to bottom area (sq. ft.) per individual. (Total stock in parentheses.)

TABLE 11.—*Sex ratio and concentration of brood stock and production of fry, September–November, 1958*

Item	Tank No. —											
	1	2	3	4	5	6	7	8	9	10	11	12
Sex ratio (♀ : ♂)	2:1	2:1	2:1	3:1	3:1	3:1	4:1	4:1	4:1	6:1	6:1	6:1
Number of fish:												
Females	20	33	47	23	38	68	24	56	72	43	60	77
Males	10	17	23	7	12	22	6	14	18	7	10	13
Total fish	30	50	70	30	50	90	30	70	90	50	70	90
Bottom area (sq. ft.):												
Per male	4.8	2.8	2.1	6.8	4.0	2.2	8.0	3.4	2.7	6.8	4.8	3.7
Per fish	1.6	1.0	0.7	1.6	1.0	0.5	1.6	0.7	0.5	1.0	0.7	0.5
Production:												
September:												
Fry produced	4,872	6,762	1,723	5,567	8,209	2,077	4,426	272	1,043	4,459	2,471	2,627
Fry per female	243.6	204.9	36.6	242.0	216.0	30.5	184.4	4.8	14.5	103.7	41.2	34.1
October:												
Fry produced	4,775	8,402	5,891	5,292	10,443	1,396	3,766	1,620	1,955	3,099	8,376	3,089
Fry per female	238.8	254.6	125.3	230.1	274.8	20.5	156.9	28.9	27.2	72.1	139.6	40.1
November:												
Fry produced	1,441	504	334	1,287	4,036	921	2,054	20	37	28	36	3,564
Fry per female	72.0	15.3	7.1	56.0	106.2	13.5	85.6	0.4	0.5	0.6	0.6	46.3
Total:												
Fry produced	11,088	15,668	7,948	12,146	22,688	4,394	10,246	1,912	3,035	7,586	10,883	9,280
Fry per female	554.4	474.8	169.1	528.1	597.0	64.6	426.9	34.1	42.2	176.4	181.4	120.5

ed to foul the tanks. On the other hand, pel-ed feed, such as pondfish and trout feed, was umed by the adult fish with little wastage. oit feed had a high percentage of crude fiber, h seemed to pass through the fish undigested left much residue in the tank. Alfalfa pellets somewhat less acceptable than the other feeds tioned, probably because of their large size their high fiber content.

n experiment to evaluate the effects of differ-types of feed in relation to fry production conducted at the Kewalo plant in September-ember, 1958. For this experiment, the three ood tanks (tanks 13, 14, and 15) were each ked with 32 males and 64 females. The adults nk 13 were fed trout feed, which we believed high in nutritional value and which was rela-y expensive. Those in tank 14 were fed rab-feed. As stated earlier, this feed was accept-to the tilapia and was also much cheaper than t feed. Preliminary trials at the pilot plant cated that relatively good fry production was ible with this feed. The fish in tank 15 were millrun, which was locally produced and the t expensive of the feeds tested.

able 12 gives the production per female for 3 months that the experiment was conducted. lot of the number of fry per female per month own in figure 13. It is evident that the fish were fed trout feed (tank 13) produced the test number of fry per female, while the fish were fed rabbit feed (tank 14) and millrun nk 15) had very low fry production.



RE 13.—Effect of type of feed given brood stock on production per female.

TABLE 12.—*Production per female in three brood tanks, by type of feed, September–November, 1958*

[Each tank stocked with 32 males and 64 females]

	Tank 13 (trout feed)	Tank 14 (rabbit feed)	Tank 15 (millrun)
September:			
Fry produced	6,863	1,874	751
Fry per female	107.2	29.3	11.7
October:			
Fry produced	13,769	1,074	529
Fry per female	215.1	16.8	8.3
November:			
Fry produced	2,695	982	394
Fry per female	42.1	15.3	6.2
Total:			
Fry produced	23,327	3,930	1,674
Fry per female	364.5	61.4	26.2

Temperature was not considered a factor in fry production in this experiment, since there was very little difference in water temperatures among the tanks. Assuming that other environmental factors were similar among the tanks, it follows from this experiment that the use of a nutritionally balanced feed is highly important in obtaining good fry production. We are not certain, however, of the long-range effect of such high-protein feeds on tilapia, which are principally herbivorous. These trout feeds are manufactured primarily for trout culturists who intend to market the fish rather than use them as brood stock—they may possibly be detrimental to spawning fish. Schaeperclaus (1933: p. 98) stated that the ovaries of trout—under intensive artificial feeding—degenerate and produce few usable eggs. It is likely that spawning stocks of tilapia held for extended periods of time should be fed a diet more in keeping with their natural food or be replaced after a year or two by a new stock of brood fish grown under more natural conditions.

SALINITY AND SPAWNING

During the summer of 1959, the Hawaii Division of Fish and Game started plans for construction of a tilapia hatchery in an area with free accesss to brackish water (about 10 °/₀₀). At the Division's request, experiments dealing with spawning and growth of young tilapia in brackish water were initiated at the Kewalo plant.

Several investigators have observed and reported that tilapia will spawn in a saline environment. Vaas and Hofstede (1952: p. 11, 16) reported that spawning occurred in a period during which the salinity of the water ranged from 3 to 4.8 percent. They pointed out, however, that "Ac-

cording to subsequent findings of the Extension Service in Indonesia, good growth is limited by a salinity of 4 percent and spawning by one of 3 percent." Brock (1954) reported tilapia spawning in sea water of a chlorinity of 19.29 °/₀₀ (equal to a salinity of about 34.85 °/₀₀) and a pH of 7.95.

Four tanks were used in this experiment: two test tanks contained brackish water and two controls contained fresh water. The experiment was started in August 1959 and terminated during the latter part of September when heavy mortalities among the adults caused by either asphyxiation or hydrogen sulfide occurred in both brackish-water tanks. Each tank was stocked with 36 females and 12 males, that is, with a 3:1 sex ratio, and at a concentration of 1 square foot per individual.

The yield of fry for the 2 months of the experiment is given in table 13. The total production was almost three times as great from the treatment tanks (brackish water) as from the controls. Analysis of variance indicated a significant difference ($F=472.65$, $P<0.05$) between fry production with respect to brackish- and fresh-water methods of culture, but no significant difference between replicates.

Exactly what influence the saline environment exerts in bringing about this increased fry production is not known, but the results of this experiment emphasize the desirability and possibilities of tilapia culture in brackish water.

TABLE 13.—*Fry production in brackish-water and fresh-water tanks, 1959*

	August	September	Total
BRACKISH WATER			
Salinity (°/₀₀):			
Minimum	8.9	9.4	
Maximum	12.3	15.2	
Average	10.9	13.2	
Tank 1:			
Fry produced	11,845	15,519	27,364
Fry per female	329.0	431.1	
Tank 3:			
Fry produced	17,319	11,745	29,064
Fry per female	481.1	326.2	
FRESH WATER			
Tank 5:			
Fry produced	6,479	1,169	7,648
Fry per female	180.0	32.5	
Tank 12:			
Fry produced	8,910	2,172	11,082
Fry per female	247.5	60.3	

FACTORS AFFECTING GROWTH OF YOUNG

The effects of environmental factors on growth of young tilapia were studied experimentally at the Kewalo plant for 12 weeks, beginning in April 1959. The effects of space or density of the fish, diet, and salinity were examined during the experiment.

We tried to vary one factor at a time, keeping the others constant, so that the single factor under observation could be evaluated with some degree of precision. We did not attempt to control the temperature, since differences among the tanks were not significant. Other factors, such as volume of water in the tank and the rate of water flow, were held as uniform as possible. In each experiment, the fish were fed at the same rate per fish regardless of lot size. An excellent quality trout feed was fed to the fish twice a day, except weekends, at the regular feeding times.

Once each week, length and weight measurements were made on a randomly collected subsample from each tank under observation. All of the fish in the subsample were returned to their respective tanks after measurements were completed. The number of fish in a subsample varied with each experiment.

We realize that, ideally, all phases of the experiments should have been conducted simultaneously. This was not possible, however, because of a lack of sufficient quantities of fry. As a result, different phases of the experiments were commenced as fry became available in adequate amounts to stock the tanks.

CONCENTRATION OF FISH AND GROWTH

A series of tests to determine the rate of growth of young tilapia in relation to their concentration, or the amount of space available for growth, was started at the Kewalo plant in April 1959. Five lots of fry, ranging in number from 1,000 to 6,000, were placed in the assault-boat tanks; however, all tanks were not stocked simultaneously.

The fish were fed trout feed (starter, fry, and small fingerling grades) for 12 weeks. The particle size and amount of feed was gradually increased as growth progressed. The fish were fed twice daily except on weekends, when they were fed once a day.

venty-five fish were measured from each of ots of 1,000, 2,000, and 3,000 fish, 40 from the f 4,000 fish, and 50 from the lot of 6,000 fish. e 14 gives the weekly averages of length and ht of fish in the randomly collected sub-ples, while figure 14 shows the regression lines l to the growth data.



RE 14.—Regression of length on time for five lots tilapia reared in various concentrations of fish in ks.

xamination of the regression coefficient from lot indicated that young in the tank stocked 1,000 fish had the best growth rate (2.9 mm. week) during the 12-week period, and that vth rates were somewhat slower with an in-sing number of fish per lot. Fish in tanks ked with 2,000 and 3,000 fry had almost tical growth rates (2.4 mm. per week) but favorable growth than the 1,000-fish lot. The of 6,000 fish, for some unknown reason, had a er growth rate than the lot containing 4,000 (2.2 and 1.8 mm., respectively, per week).

tatistically, the differences in growth among five lots of fish were significant ($F=41.92$, 0.01). From the results of the experiment, it ows that the ideal stocking density for nursery ers (fry tanks) would be 9 fry per cubic foot 5 fry per square foot of surface area (1,000-

TABLE 14.—*Weekly average length (mm.) and weight (g.) and average absolute growth rates in random subsamples of tilapia from various concentrations of fry, 1959*

	1,000 fry	2,000 fry	3,000 fry	4,000 fry	6,000 fry
Experiment began	May 29	May 29	Apr. 9	May 22	Apr. 9
Experiment ended	Aug. 21	Aug. 21	July 2	Aug. 14	July 2
Initial length	12.4	12.0	11.9	11.8	11.9
Initial weight	0.024	0.012	0.024	0.012	0.024
1st week:					
Length	17.0	14.5	13.6	13.5	12.8
Weight	0.072	0.040	0.040	0.030	0.040
2d week:					
Length	19.2	16.7	17.6	16.0	15.7
Weight	0.116	0.068	0.096	0.052	0.062
3d week:					
Length	23.5	21.2	19.3	18.3	16.8
Weight	0.168	0.148	0.094	0.092	0.062
4th week:					
Length	25.1	21.5	25.0	19.7	21.1
Weight	0.284	0.176	0.272	0.115	0.148
5th week:					
Length	28.3	26.1	27.2	21.7	24.0
Weight	0.400	0.320	0.308	0.152	0.224
6th week:					
Length	30.3	28.0	28.4	26.2	25.3
Weight	0.480	0.400	0.416	0.312	0.264
7th week:					
Length	33.2	29.9	30.6	25.7	28.4
Weight	0.640	0.492	0.500	0.300	0.432
8th week:					
Length	34.7	29.6	33.5	28.6	29.2
Weight	0.792	0.500	0.705	0.412	0.484
9th week:					
Length	39.1	33.4	34.5	31.1	31.9
Weight	1.116	0.692	0.780	0.578	0.628
10th week:					
Length	42.7	36.6	36.2	32.2	33.2
Weight	1.448	0.960	0.844	0.605	0.670
11th week:					
Length	43.8	37.8	38.4	32.5	34.8
Weight	1.596	0.964	0.964	0.615	0.708
12th week:					
Length	49.8	42.8	40.7	30.8	37.8
Weight	2.408	1.528	1.280	0.612	0.972
Average absolute growth rate	3.1 mm.	2.6 mm.	2.4 mm.	1.6 mm.	2.2 mm.

fish lot). Some lesser concentration, as yet undetermined, might prove even better. However, from a practical standpoint, these very low stocking rates might not be the most feasible economically, as the space requirements and construction costs for fry-rearing tanks would be enormous in a commercial operation.

Earlier, we mentioned that newly emerged fry almost always were captured near the surface of the water. Upon transfer to nursery waters, the fry continue to exhibit this behavior. Therefore, we believe that stocking density should be related to surface area rather than to volume of water.

DIET AND GROWTH

An experiment to compare the growth rates obtained on an inexpensive, commercially available feed and the more expensive, but highly nutritious, trout feed was initiated in April 1959 simultaneously with the experiment on relation of space to growth at the Kewalo plant. An as-

sault-boat tank was stocked with 3,000 fry and fed exclusively with wheat white middlings, a locally available livestock feed, while the lot of 3,000 fry in the space-growth experiment was fed trout feed.

The weekly average lengths and weights of a random subsample of 25 fish from each of the two lots, for the 12-week period of the experiment, are presented in table 15. Regression lines were fitted

TABLE 15.—*Weekly average length (mm.) and weight (g.) and average absolute growth rates in random subsamples of tilapia from 2 lots of 3,000 fry reared on different diets, 1959*

Item	Trout feed	Wheat white middlings
Experiment began	Apr. 9	May 15
Experiment ended	July 2	Aug. 7
Initial length	11.9	12.1
Initial weight	0.024	0.014
1st week:		
Length	13.6	13.7
Weight	0.040	0.032
2d week:		
Length	17.6	16.9
Weight	0.096	0.064
3d week:		
Length	19.3	18.9
Weight	0.094	0.104
4th week:		
Length	25.0	21.0
Weight	0.272	0.160
5th week:		
Length	27.2	21.5
Weight	0.308	0.144
6th week:		
Length	28.4	23.5
Weight	0.416	0.424
7th week:		
Length	30.6	27.1
Weight	0.500	0.392
8th week:		
Length	33.5	28.6
Weight	0.705	0.380
9th week:		
Length	34.5	30.3
Weight	0.780	0.520
10th week:		
Length	36.2	31.7
Weight	0.844	0.620
11th week:		
Length	38.4	34.0
Weight	0.964	0.672
12th week:		
Length	40.7	33.9
Weight	1.280	0.768
Average absolute growth rate	2.4 mm.	1.8 mm.

to the growth obtained in these tanks. The regression coefficient for the lot fed trout feed was 2.4 mm. per week while that for the lot fed wheat white middlings was 1.9 mm. per week (fig. 15). An analysis of variance of the results disclosed a significant difference in growth rates between the fish in the two tanks ($F=31.09$, $P<0.01$), indicating that quality of the feed is highly important where fast growth rates are desired.



FIGURE 15.—Regression of length on time for two lots of fish reared on different diets.

SALINITY AND GROWTH

It has been reported by Vaas and Hofstede (1952) and Brock (1954) that *T. mossambica* will spawn and the young will grow in salt water. To determine growth rates under varying degrees of salinity, preliminary experiments were conducted at the Kewalo plant laboratory using 30-gallon aquariums.

Five 30-gallon aquariums were used in the experiment: two containing fresh water, two brackish water (salinity of about 16 °/₀₀, and one sea water. Each aquarium was stocked with 200 fry. Those fish to be tested in brackish water and in sea water were acclimatized to sea water for a period of 24 hours before being placed in the aquariums. The fish in one tank in each pair of the fresh-water and brackish-water aquariums were fed wheat white middlings, while fish in the other two tanks and in the sea-water tank were fed trout feed (starter).

From the first week, a large number of deaths occurred in the brackish- and sea-water tanks and the deaths continued to occur for several weeks. At first, the dead fish in each of the tanks were removed and counted each morning and replaced with an equal number of individuals of similar size from a reserve stock which was held in sea water in another aquarium. Because of the high mortality rate and the low growth rate in all the

LE 16.—*Differences in average length (mm.), weight) and average absolute growth rates of 5 lots of 200 fish, relation to types of water and feed*

Item	Aquarium No.—				
	1	2	3	4	5
of water	Fresh	Fresh	Brackish	Brackish	Sea.
of feed	Trout	Wheat white mid-dlings.	Trout	Wheat white mid-dlings.	Trout.
l length of y	12.8	13.3	13.3	13.2	13.0.
l weight of	0.03	0.03	0.03	0.03	0.03.
h at 5 weeks	17.9	18.3	17.8 [1]	18.0	18.2.
nt at 5 weeks	0.12	0.12	0.10	0.12	0.14.
age absolute wth rate	1.02 mm.	1.00 mm.	0.90 mm.	0.96 mm.	1.04 mm.
deaths	66	95	122	208	333.

nese figures are based on length-weight measurements at end of the n week.

erimental tanks, the experiment was termi-ed at the end of 5 weeks.

A random subsample of 10 fish was collected n each aquarium and the fish measured once h week during the 5-week period (table 16). e results were not suitable for statistical analy-

A general summary (table 16) shows that rtality was lowest in fresh water and highest sea water. Differences in growth rate were ght and most likely of no biological significance.

A second experiment, which dealt with the cts of salinity on growth of the young, was ducted simultaneously with the experiment on



URE 16.—Regression of length on time for young tilapia reared in brackish and in fresh water.

the effect of salinity on the rate of reproduction.

Four assault-boat tanks, two containing brackish water with a salinity of about 10 °/₀₀ and two with fresh water serving as controls, were stocked simultaneously with 4,000 fry. The fish were fed trout feed twice a day. Salinity determinations (by hydrometer) of the brackish-water tanks were made daily (table 13 lists average and range of salinities for the 2 months of the experiment). Length and weight measurements were made weekly for 8 weeks on a random subsample of 40 fish from each tank. The results of the experiment are recorded in table 17, while the regression lines describing the growth in each tank are shown in figure 16.

It is evident from the regression coefficients that the brackish-water environment had a pronounced influence on the growth rate of the young fish. Here again, we are not certain of the effect of the saline environment on young tilapia, but presumably it alters metabolic processes enough to affect growth considerably. An analysis of variance indicated a significant difference in growth between treatments ($F=39.94, P<0.01$), and no significant difference in growth between replicates.

Another interesting aspect of this experiment was that the growth rates of the fish in the fresh-

TABLE 17.—*Average length (mm.) and weight (g.) and average absolute growth rates of random subsamples of tilapia from 4 lots of 4,000 fry reared in brackish and fresh water*

Item	Brackish water		Fresh water	
	Tank 2	Tank 4	Tank 6	Tank 11
Initial length	12.4	12.6	12.0	12.1
Initial weight	0.028	0.030	0.025	0.025
1st week:				
Length	14.1	13.5	15.2	13.5
Weight	0.042	0.040	0.055	0.042
2d week:				
Length	15.8	15.5	17.6	15.2
Weight	0.070	0.072	0.080	0.065
3d week:				
Length	21.6	19.8	20.2	17.5
Weight:	0.178	0.145	0.265	0.225
4th week:				
Length	26.2	25.3	23.8	21.0
Weight	0.295	0.280	0.242	0.145
5th week:				
Length	31.2	29.9	25.4	26.5
Weight	0.548	0.500	0.300	0.380
6th week:				
Length	33.4	34.5	28.8	29.3
Weight	0.772	0.892	0.490	0.512
7th week:				
Length	39.2	38.1	32.0	33.4
Weight	1.200	1.100	0.632	0.712
8th week:				
Length	42.8	41.8	34.1	36.0
Weight	1.412	1.378	0.682	0.870
Average absolute growth rate	3.8 mm.	3.6 mm.	2.8 mm.	3.0 mm.

water control tanks compared favorably with the growth rates of the 1,000-fish lot in the space-growth experiment. We expected that the growth rates in the control tanks would be somewhat similar to those experienced in the 4,000-fish lot of the space-growth experiment. The growth rates in the two control tanks were 3.2 and 2.8 mm. per week over an 8-week period, while the growth rate of the 4,000-fish lot was 2.1 mm.

The fish were raised under seemingly identical conditions, except for the time of year that the experiment was conducted. The 4,000-fish lot was reared from mid-May to mid-August, while the control-tank lots were reared in August and September. Although there are no temperature records for these growth experiments, the temperature record of the heating experiment (table 8) discloses a difference of about 4° F between May and August in control tank 13. Presumably, this difference also applied to the assault-boat tanks. Therefore, it is quite reasonable to conclude that water temperature is important in obtaining fast growth; however, the optimum temperature has not been determined.

Some other factor, possibly environmental, chemical, or genetic, acting singly or in combination with temperature may also have contributed to this discrepancy in growth rates. The end results of the salinity-growth experiment paralleled the results of the salinity-spawning experiment, however, indicating that a commercial rearing plant can, and should be operated on a brackish-water system, thereby reducing or eliminating the high cost of using fresh water.

CANNIBALISM AND PREDATION

Cannibalism and predation are important factors in the successful rearing of young tilapia. Our initial plan to rear tilapia fry to bait-fish size in a single large fry tank met with a major setback when about 2 months after production started we discovered juveniles, ranging in length from 25 to 38 mm. (1 to 1.5 in.), chasing and consuming newly emerged fry that were being released into the tank. This situation was remedied by installing Monel-screen partitions to separate the tank into three compartments and segregate the young according to size. Cannibalism among tilapia was also reported by Chen (1953). The results of his observations are summarized in table 18.

TABLE 18.—*Size relation between intraspecific predator and prey in* T. mossambica

[Data from Chen (1953)]

Size of predator	Size of prey
0.75 inch	Up to 0.38 inch.
3 to 6 inches	Up to 0.5 inch.
7 inches	Up to 1.25 inches.

In order to extend the findings of Chen and further define this intraspecific, predator-prey size relation, the following experiments were conducted in 35-gallon aquariums. Eight juvenile groups (predator) of different average lengths were selected. The average length of the groups ranged from 20.4 to 64.4 mm. (about 0.75 to 2.5 in.). A predator group consisting of 10 juveniles was first measured and placed in an aquarium. A second group of 20 to 30 young (prey), all fry or fry and juveniles, was also measured and placed in the same aquarium. Each of the eight experiments was carried out for a period of 72 hours, after which time the remaining prey were removed and measured. The fish did not receive any supplementary feeding during the period of the experiment. By comparing the lengths of the remaining young with the lengths of the young that were put into the aquarium, we were able to determine the maximum size of the young that were killed or consumed by each size group of predators. The results are given in table 19 and figure 17.



FIGURE 17.—Relation between size of juvenile groups (predators) and maximum size of young killed or consumed.

E 19.—*Size of young (prey) killed and consumed by different juvenile groups (predator)*

juvenile group consisted of 10 fish of approximately equal size]

Length of predator group (mm.)		Length of prey group (mm.)	
ange	Average	Range	Maximum size killed
3–23.7	20.4	9.7–12.5	10.0
2–29.6	27.6	10.2–15.6	12.7
4–36.4	33.2	9.8–19.2	16.2
9–42.3	40.0	10.3–19.2	15.0
2–48.7	46.7	9.8–20.0	17.0
4–54.8	51.0	9.0–21.2	18.5
7–61.4	58.0	9.0–29.0	22.5
0–67.8	64.4	9.2–29.0	24.5

her experiments with starved and well-fed niles showed that the degree of cannibalism eases when the fish are starved. One par- ar group of 50 juveniles, averaging 31.8 mm. 5 in.) in length, when well fed consumed 9 veraging 11.1 mm. (0.44 in.) in 15 minutes. same group, when starved for a period of 3 , killed or consumed 17 fry averaging 14.3 (0.56 in.) in 12 minutes. When starved, the niles were aggressive upon introduction of the whereas when well fed they were not par- larly excited by appearance of the fry and rally remained near the bottom of the tank. ggressive response by well-fed juveniles was ceable only when a single fry or group of fry oached closely.

hese experiments indicated the importance of ing each compartment of the fry tank stocked young fish of uniform size.

nother source of attrition, although not sidered so important as cannibalism, was lation by dragonfly nymphs. These highly acious larvae, which occurred commonly in fry and assault-boat tanks, usually preyed on smaller fry. Considerable effort was made to ove these nymphs. Chemical means of control t, potassium permanganate, and pyridyl- curic acetate, commonly called PMA) proved fective; dipnetting them individually seemed most effective method.

SUMMARY AND CONCLUSIONS

his study evaluates the physical and biological ibility of producing bait-size tilapia in tanks. o facilities were used during the experiments. first facility, or pilot plant, constructed on the grounds of the Bureau of Commercial Fisheries Biological Laboratory at Honolulu, Hawaii, was used from October 1956 to July 1958; the second, at the Kewalo Basin docksite, Honolulu, was used from August 1958 until September 1959. Results obtained at the pilot plant were of a preliminary and general nature, but aided in planning the more detailed experiments designed to examine factors associated with variations in reproduction and growth at the Kewalo plant.

Brood tanks at the pilot plant were stocked at the rate of 0.9 and 1.9 square feet of floor area per individual and with a sex ratio of 2 ♀ : 1 ♂. Stocking of the Kewalo tanks varied from 0.5 to 1.6 square feet of bottom area per individual, and the sex ratios (♀ : ♂) were 2 : 1, 3 : 1, 4 : 1, and 6 : 1.

Supplementary feeding of the tilapia included rice bran, chicken mash, alfalfa pellets, rabbit feed, and pelletized pond-fish feed and trout feed. Generally, for the adults pelletized feeds were much more satisfactory than finely divided mash and bran. Young fish were fed finely ground pondfish and trout feed.

Chemical analyses to determine concentrations of oxygen, free carbon dioxide, total bicarbonate and carbonate alkalinity, and hydrogen-ion were made routinely at weekly intervals to follow gross changes in the environment within the tanks.

Fry production at the pilot plant started in December 1956, approximately 9 weeks after the initial stocking. Nest-building activity was noted only after 3 to 4 inches of calcareous beach sand was placed in two of the brood tanks. Evidence of spawning on the bare floor, however, was noted when the one tank without sand was drained.

At both rearing plants, as the young emerged each day they were captured with a fine-meshed dipnet and counted. They were then placed in a fry tank and segregated by size in different compartments to prevent cannibalism.

Mortalities among the adults were attributable to factors such as handling, disease, asphyxiation, and possibly hydrogen sulfide poisoning. Highest mortality rates among the young were attributed to outbreaks of infectious disease and infestation by ectoparasites. Infestation by protozoan ectoparasites such as trichodinids and *Chilodon* spp. was rather easily controlled by chemical treat-

ment. Outbreaks of infectious pancreatic necrosis, believed to be caused by a virus, were not controlled by any of the methods tried. Strict sanitation, prevention of overcrowding in the fry-tank compartments, and periodic prophylactic treatments were found to be good control measures for preventing outbreaks of disease.

Several factors were found to affect fry production. The spawning rate was increased during the winter months by artificially raising the temperature of the water. Only a slight rise was necessary to increase spawning frequency, but prolonged constant high temperature seemed to have a detrimental effect.

A sex ratio of 3 ♀ : 1 ♂ resulted in the highest reproductive rate. An allotment of about 4.0 square feet of bottom area per male and 1.0 square foot per individual provided the most optimum conditions for courtship and spawning. Brood stocks fed high-quality feed had higher production per female than those fed low-quality feed. A significantly higher fry production occurred in brackish water (about 10 °/₀₀) than in fresh water.

The growth of young fish was influenced by environmental factors. Significantly faster growth rates were found among young reared in less crowded tanks than in crowded tanks. Young reared on high-quality feed also evinced a much faster growth rate than those fed low-quality feed. The growth of young fish in brackish water of a salinity of about 10 °/₀₀ was remarkably fast.

An investigation of cannibalism indicated that juveniles averaging 20.4 mm. (about 0.75 in.) can kill or consume fry up to 10 mm. (about 0.38 in.) in length, and juveniles averaging 64.4 mm. (about 2.5 in.) in length are able to kill or consume smaller juveniles up to a maximum size of 24.5 mm. (about 1 in.). Starved juveniles evinced a much more aggressive response than well-fed juveniles to fry introduced into their tanks.

LITERATURE CITED

Atz, James W.
1954. The peregrinating tilapia. Animal Kingdom, vol. 57, no. 5, p. 148–155.

Baerends, G. P., and J. M. Baerends–Van Roon.
1950. An introduction to the study of the ethology of cichlid fishes. Behaviour, Supplement 1, 243 p.

Brock, Vernon E.
1954. A note on spawning of *Tilapia mossambica* in sea water. Copeia, 1954, no. 1, p. 72.

Brock, Vernon E., and Michio Takata.
1955. Contribution to the problems of bait fish capture and mortality, together with experiments in the use of tilapia as live bait. Territory of Hawaii, Industrial Research Advisory Council Grant No. 49, Final Report, 39 p.

Chen, Tung–Pai.
1953. The culture of tilapia in rice paddies in Taiwan. Chinese American Joint Commission on Rural Reconstruction, Fisheries Series, no. 2, 30 p.

Chimits, Pierre.
1955. Tilapia and its culture—a preliminary bibliography. Food and Agricultural Organization, Fisheries Bulletin, vol. 8, no. 1, p. 1–33.
1957. The tilapias and their culture. Food and Agricultural Organization, Fisheries Bulletin, vol. 10, no. 1, p. 1–24.

Davis, Herbert S.
1946. Care and diseases of trout. Revised ed. U.S. Fish and Wildlife Service, Research Report 12, 98 p.
1953. Culture and diseases of game fishes. University of California Press, Berkeley, 332 p.

Doudoroff, Peter.
1957. Water quality requirements of fishes and effects of toxic substances. The Physiology of Fishes. Vol. 2, Behavior. Academic Press, Inc., New York, p. 403–430.

Fish, G. R.
1955. The food of tilapia in E. Africa. Uganda Journal, vol. 19, no. 1, p. 85–89.

Hida, Thomas S., Joseph R. Harada, and Joseph E. King.
1962. Rearing tilapia for tuna bait. U.S. Fish and Wildlife Service, Fishery Bulletin 198, vol. 62, p. 1–20.

Innes, William T.
1951. Exotic aquarium fishes. 12th ed. Innes Publishing Co., Philadelphia, 521 p.

June, Fred C.
1951. Preliminary fisheries survey of the Hawaiian–Line Islands area. Part III. The live-bait skipjack fishery of the Hawaiian Islands. U.S. Fish and Wildlife Service, Commercial Fisheries Review, vol. 13, no. 2, p. 1–18.

King, Joseph E., and Peter T. Wilson.
1957. Studies on tilapia as skipjack bait. U.S. Fish and Wildlife Service, Special Scientific Report—Fisheries No. 225, 8 p.

Lagler, Karl F.
1956. Freshwater fishery biology. 2d ed. Wm. C. Brown Co., Dubuque, Iowa, 421 p.

Le Roux, P. J.
1956. Feeding habits of the young of four species of tilapia. South African Journal of Science, vol. 53, no. 2, p. 33–37.

Lowe, Rosemary H.
1955. The fecundity of tilapia species. East African Agricultural Journal, vol. 21, no. 1, p. 45–52.

, Eugene P.
959. Fundamentals of ecology. 2d ed. W. B. Saunders Co., Philadelphia, 546 p.
KKAR, N. Kesava, and P. R. S. Tampi.
954. On the mouth-breeding cichlid, *Tilapia mossambica* Peters. Indian Journal of Fisheries, vol. 1, nos. 1–2, p. 217–230.
EPERCLAUS, Wilhelm.
933. Textbook of pond culture; rearing and keeping of carp, trout and allied fishes. Book Publishing House Paul Parey, Berlin. (Translated from the German by F. Hund; *in* U.S. Fish and Wildlife Service, Fishery Leaflet 311, 260 p. Processed, 1948.)
STER, Walter H.
952. Fish-culture in brackish-water ponds of Java. Indo-Pacific Fisheries Council, Special Publication No. 1, 143 p.
SZKO, S. F., and Ken Wolf.
958. Infectious pancreatic necrosis of salmonid fishes (acute catarrhal enteritis). U.S. Fish and Wildlife Service, Fishery Leaflet 453, 3 p.
GLE, H. S.
1957. Further experiments with *Tilapia mossambica* as a pondfish. Alabama Polytechnic Institute, Agricultural Experiment Station, Auburn, 6 p. [Mimeographed.]
1960. Comparative evaluation of two tilapias as pondfishes in Alabama. Transactions of the American Fisheries Society, vol. 89, no. 2, p. 142–148.

Tester, Albert L., Heeny Yuen, and Michio Takata.
1954. Reaction of tuna to stimuli, 1953. U.S. Fish and Wildlife Service, Special Scientific Report—Fisheries No. 134, 33 p.

Vaas, K. F., and A. E. Hofstede.
1952. Studies on *Tilapia mossambica* Peters (ikan mudjair) in Indonesia. Contributions of the Inland Fisheries Research Station, Djakarta-Bogor, Indonesia, No. 1, 68 p.

Van Pel, H.
1955. Pond culture of tilapia. South Pacific Commission, Quarterly Bulletin, vol. 5, no. 3, p. 30–31.

Welch, Paul S.
1935. Limnology. 1st ed. McGraw-Hill Book Co., New York, 471 p.

Yamashita, Daniel T.
1958. Analysis of catch statistics of the Hawaiian skipjack fishery. U.S. Fish and Wildlife Service, Fishery Bulletin 134, vol. 58, p. 253–278.

APPENDIX

APPENDIX TABLE 1.—*Oxygen concentrations (ml./l.) at the pilot plant, determined weekly, April 2, 1957–July 8, 1958*

Date	Zone time	Tank No. —			Assault-boat[1] tank No. —				Fry tank	Tap water
		1	2	3	1	2	3	4		
1957:										
Apr. 2	0900	0.75	3.87	4.61						4.29
9	1000	4.75	6.75	5.71						6.06
16	1000	2.67	5.80	3.81						6.08
23	1000	4.88	5.56	3.90						5.97
30	1000	3.72	5.30	4.80						5.32
May 7	1100	2.94	5.25	3.75						6.17
14	1000	0.77	2.56	2.87						6.09
21	1000	3.36	2.59	2.70						5.68
28	1000	3.33	3.64	3.34						6.36
June 4	1000	1.68	2.03	2.42						6.15
11	1000	3.16	2.78	2.70						6.08
19	1000	0.63	0.54	1.10						6.08
26	1000	1.12	0.54	1.56						6.08
July 2	1000	2.68	0.96	4.22						6.06
9	1000	3.58	3.30	3.76						6.48
16	0830	1.78	1.73	3.42		5.40	2.40	3.53		5.88
23	0830	3.78	3.34	5.40		5.19	1.90	3.69	1.05	6.12
31	1000	5.60	6.96	6.54	4.38	4.34	3.25	4.30	5.14	5.70
Aug. 6	0830	1.34		2.51	3.10	4.02	3.77	2.46	4.37	5.57
13	0830	1.30	2.76	1.40		3.66	3.59		3.57	5.84
22	1000	5.22	4.33	2.59	6.51	3.43	5.49		4.11	5.84
28	0830	0.62	1.95	1.40	5.14	4.12	4.84	4.52	4.64	5.91
Sept. 5	0830	1.81	3.04	3.33	5.64	4.00	5.72	4.70	4.11	5.64
10	0830	0.74	1.23	2.75	4.86	4.27	4.77	4.53	3.54	5.79
18	0830	1.18	0.92	1.39	4.86		2.96		2.77	5.68
25	0830	0.85	1.17	1.65	5.52	2.69			3.36	5.78
Oct. 3	0830	0.87	1.31	1.41	5.79	4.42	2.63		3.77	5.83
11	0830	0.56	0.85	3.13	5.42	3.85	2.11		4.20	5.84
16	0830	0.58	0.72	1.49	5.48	4.18	1.90	2.46	4.75	5.72
23	0830	0.85	1.35	1.55	4.57		1.56	1.05	3.38	6.01
30	0830	2.68	1.37	2.41	4.44	3.67	0.95	0.93	5.00	6.05
Nov. 6	0830	0.90	6.42	3.97	6.31	5.66	2.66	2.06	6.81	6.03
12	0800	1.17	0.78	1.84	4.36	2.77	0.74	0.73	3.00	5.99
20	0845	1.44	2.57	2.45	5.27	3.84	1.69	0.61	3.08	6.17
Dec. 3	1000	2.40	3.75	2.80	5.48	5.02	4.64		5.44	5.93
10	1000	4.22	6.34	2.14	5.72	5.18	4.54		5.82	5.92
20	1100	3.74	6.16	2.36						
26	0900	0.40	1.86	1.83	4.79			5.54		6.12
1958:										
Jan. 9	1300	3.24	7.93	2.46		5.95			6.97	6.22
16	1000	0.56	0.26	2.18		6.23			6.48	6.46
24	0815	0.38	0.90	2.42		5.77			5.76	5.71
Feb. 6	1300	4.20	3.13	5.21					6.96	6.21
14	1000	0.51	1.07	1.07					5.85	6.42
28	1300	5.65	6.74	2.42					7.04	6.09
May 26	0800	0.64	0.69	0.34					5.66	
June 12	0800	0.46	0.19	0.28						6.05
17	0830	1.60	0.97	0.38						5.80
24	0815	0.64	0.10	0.35						5.95
July 2	0815	1.26	1.15	0.06					5.45	
8	0800	1.15	0.91	0.85					5.46	

[1] Acquired June 1957.

NDIX TABLE 2.—*Oxygen concentrations in tanks 1 and 2 sampled hourly for 24 hours, at the pilot plant, November 12–13 1957*

Zone time	Tank 1 [1]		Tank 2 [2]		Cloud cover	Comments
	Oxygen (ml./l.)	Temperature (° F.)	Oxygen (ml./l.)	Temperature (° F.)		
	1.17	73.5	0.78	74.5	6/8	Sun clouded over.
	1.50	74.0	4.71	75.0	4/8	Tanks partly exposed to sunlight.
	2.00	75.0	5.57	76.0	3/8	Tanks fully exposed to sunlight.
	2.46	76.0	8.08	77.0	2/8	Do.
	2.83	77.5	10.46	78.5	1/8	Do.
	3.32	78.5	12.24	79.5	1/8	Tanks 1/4 shaded from sunlight.
	3.59	79.0	12.36	80.0	1/8	Tanks 1/2 shaded from sunlight.
	3.49	78.5	11.31	80.0	1/8	Tanks almost entirely shaded from sunlight.
	3.22	78.5	9.45	80.0	2/8	Tanks completely shaded from sunlight.
	3.01	78.0	8.21	79.0	2/8	Do.
	2.65	77.5	6.98	79.0	Dark	Dark.
	2.12	77.0	5.66	78.5	do	Do.
	1.82	76.5	4.99	76.0	do	Do.
	1.46	76.5	4.30	76.0	do	Do.
	1.24	76.0	3.84	76.0	do	Do.
	1.08	76.0	3.27	76.0	do	Do.
	0.94	75.5	3.06	76.5	do	Do.
	0.86	75.5	2.80	76.5	do	Do.
	0.69	75.5	2.56	76.5	do	Do.
	0.50	75.0	2.26	76.0	do	Do.
	0.46	74.5	2.00	75.5	do	Do.
	0.43	74.5	1.88	75.5	do	Do.
	0.38	74.0	1.54	75.0	do	Daylight visible at 0620.
	0.37	74.0	1.23	75.0	1/8	Sunlight visible.
	0.42	74.0	1.17	75.0	1/8	Tanks partly exposed to sunlight.
	0.48	74.0	1.33	75.0	1/8	Tanks almost all exposed to sunlight.

Tank 1 was cleaned on Nov. 4, 1957 and the water was still relatively low in algae on Nov. 12 and 13.
Tank 2 had a high concentration of algae (*Chlorella*).

ENDIX TABLE 3A.—*Oxygen concentrations (ml./l.) observed in sex ratio-fish concentration experiment, August 27–November 26, 1958*

Date	Zone time	Tank 1	Tank 2	Tank 3	Tank 4	Tank 5	Tank 6	Tank 7	Tank 8	Tank 9	Tank 10	Tank 11	Tank 12
27	0830	5.65	1.68	5.36	3.18	3.28	2.63	4.90	3.80	3.62	2.24	4.69	3.66
4	0830	4.04									1.62		4.18
12	0815	1.53						3.57					1.83
19	0810	3.00									2.84		1.10
2	0815				2.48		3.65		0.36				
9	0815	1.75								2.72	1.25		
16	0815				1.98	0.43							1.00
23	0800				0.80	1.54							0.81
30	0800				2.74	0.76							1.82
6	0800	2.45						2.22					2.03
13	0800	1.58			0.81					1.16			
20	0800	3.90				0.30				1.54			
26	0800					1.44					1.06		2.87

APPENDIX TABLE 3B.—*Oxygen concentrations (ml./l.) observed in feeding experiment, August 27–November 26, 1958*

Date	Zone time	Tank 13	Tank 14	Tank 15	Tap water
Aug. 27	0830	1.17	1.94	1.04	
Sept. 4	0830	2.81			5.74
12	0815	1.09			
19	0810	2.31			
Oct. 2	0815		0.99		5.96
9	0815			1.68	5.56
16	0815		1.15		5.58
23	0800		0.86		6.00
30	0800			2.98	5.84
Nov. 6	0800			1.69	6.57
13	0800			0.97	5.96
20	0800		1.83		6.68
26	0800		1.45		6.30

APPENDIX TABLE 4.—*Oxygen concentrations (ml./l.) in tanks 13, 14, and 15 during heating experiment, January 16–August 27, 1959*

Date	Zone time	Tank 13	Tank 14 (with heating cable and cover)	Tank 15 (with heating cable only)	Tap water
Jan. 16	0815	6.69	0.80	4.72	5.96
23	0800	2.49	0.69	2.57	6.03
28	0800	1.51	0.78	0.83	5.99
Feb. 5	0800	3.11	3.04	4.94	5.76
12	0800	0.91	0.95	1.17	5.82
19	0815	3.97	3.59	3.09	6.32
26	0800	5.32	4.14	4.39	6.53
Mar. 5	0805	5.06	1.86	5.09	6.00
12	0800	4.83	2.11	4.05	4.89
19	0800	4.49	3.56	4.84	5.96
26	0800	3.01	1.37	4.87	7.74
Apr. 2	0800	3.49	1.64	2.86	5.95
9	0800	2.96	5.58	2.04	6.30
16	0800	1.23	2.77	1.53	6.30
23	0800	1.72	2.63	3.28	6.28
30	0810	1.76	2.84	2.27	6.20
May 7	0810	3.32	2.27	2.98	5.98
14	0810	2.54	3.72	4.05	6.10
21	0800	2.46	2.95	3.01	6.06
28	0810	3.01	3.54	4.46	6.10
June 4	0815	4.20	4.43	4.55	6.12
11	0815	4.45	4.36	4.46	5.98
18	0810	3.54	3.79	3.93	5.99
25	0800	4.29	3.99	4.99	5.85
July 2	0800	5.45	2.83	5.39	6.18
9	0800	4.35	2.40	2.92	5.99
16	0800	4.20	1.31	3.55	6.10
23	0800	3.06	2.63	3.34	5.96
30	0800	2.53	1.86	3.40	5.

APPENDIX TABLE 4.—*Oxygen concentrations (ml./l.) in tanks 13, 14, and 15 during heating experiment, January 16–August 27, 1959*—Continued

Date	Zone time	Tank 13	Tank 14 (with heating cable and cover)	Tank 15 (with heating cable only)	Tap water
Aug. 6	0800	2.08	1.51	2.69	6.26
13	0800	4.92	0.84	1.60	5.98
20	0800	4.42	1.53	3.00	5.70
27	0800	3.71	0.89	1.18	5.97

APPENDIX TABLE 5.—*Oxygen concentrations (ml./l.) in brackish-water and fresh-water tanks, during salinity-spawning experiment, August 6–September 24, 1959*

Date	Zone time	Tank 1 (brackish water)	Tank 5 (fresh water)	Tap water
Aug. 6	0800	4.95	2.63	6.26
13	0800	4.16	2.08	5.98
20	0800	3.21	1.13	5.70
27	0800	3.22	1.42	5.97
Sept. 3	0800	1.82	0.61	7.25
10	0800	1.18	1.44	5.56
17	0815	4.11	1.28	6.05
24	0800	0.90	2.34	6.34

APPENDIX TABLE 6A.—*Hydrogen-ion (pH) values observed in sex ratio-fish concentration experiment, October 2–November 26, 1958*

Date	Zone time	Tank 1	Tank 2	Tank 3	Tank 4	Tank 5	Tank 6	Tank 7	Tank 8	Tank 9	Tank 10	Tank 11	Tank 12
Oct. 2	0800	7.7	8.1	8.2	7.9	8.6	7.7	8.6	7.3	7.7	8.3	7.9	7.9
9	0800	7.9	7.7	7.7	8.5	7.7	7.3	7.6	7.6	7.7	7.5	7.4	7.7
16	0800	8.8	8.1	7.7	8.7	7.4	7.7	7.5	7.6	7.3	7.6	7.5	7.6
23	0800	7.9	7.4	7.4	7.4	7.8	7.4	7.8	7.5	7.3	7.5	7.5	7.3
30	0800	>8.8					>8.8	>8.8					8.1
Nov. 6	0800	>8.8				8.4				7.9			8.0
20	0800	8.7	8.3	8.7	8.8	7.9	>8.8	>8.8	>8.8	8.7	8.5	8.7	8.1
26	0800	8.6	7.7	7.9	>8.8	7.4	7.9	8.7	8.1	7.7	7.6	8.4	8.7

APPENDIX TABLE 6B.—*Hydrogen-ion (pH) values observed in feeding experiment, October 2–November 26, 1958*

Date	Zone time	Tank 13	Tank 14	Tank 15	Tap water
Oct. 2	0800	8.6	7.4	7.7	8.0
9	0800	8.7	7.7	7.7	8.2
16	0800	8.7	7.6	8.1	8.2
23	0800	7.7	7.5	7.5	8.3
30	0800		8.3		
Nov. 6	0800		7.7		
20	0800	8.4	8.1	8.2	8.1
26	0800	8.1	7.6	7.9	

ENDIX TABLE 7.—*Hydrogen-ion (pH) values during ating experiment, determined weekly, January 16–ugust 27, 1959*

Date	Zone time	Tank 13 (control)	Tank 14 (with heating cable and cover)	Tank 15 (with heating cable only)	Tap water
6	0815	8.7	7.7	8.6	----------
3	0800	8.4	7.8	8.3	----------
8	0800	7.8	7.5	7.9	8.1
5	0800	8.8	8.1	8.8	8.1
2	0800	7.4	7.4	7.6	8.1
9	0815	7.6	7.6	8.8	----------
5	0800	7.9	8.0	8.4	7.9
5	0805	7.7	7.5	7.9	8.2
2	0800	8.0	7.5	8.0	8.1
9	0800	7.9	7.7	8.1	8.1
6	0800	7.7	7.5	7.9	8.3
2	0800	7.7	7.5	7.9	8.3
9	0800	7.7	7.9	8.1	8.1
5	0800	----------	7.7	----------	8.3
8	0800	7.7	7.4	7.7	8.1
0	0810	8.4	7.9	8.3	8.1
7	0810	7.9	7.8	----------	8.1
14	0810	8.1	8.1	8.7	8.3
21	0800	7.9	----------	8.4	8.1
28	0810	7.7	7.9	8.1	7.9
4	0815	7.9	8.1	8.5	7.9
11	0815	8.2	8.1	8.2	7.9
18	0810	8.1	8.1	8.1	7.9
25	0800	8.1	7.7	7.9	8.1
2	0800	7.8	7.5	7.7	7.9
9	0800	8.1	7.6	7.4	7.9
16	0800	8.3	7.4	7.5	7.9
23	0800	7.5	7.4	7.5	7.9
30	0800	7.8	7.5	7.7	7.9

APPENDIX TABLE 7.—*Hydrogen-ion (pH) values during heating experiment, determined weekly, January 16–August 27, 1959*—Continued

Date	Zone time	Tank 13 (control)	Tank 14 (with heating cable and cover)	Tank 15 (with heating cable only)	Tap water
Aug. 6	0800	7.3	7.3	7.4	8.2
13	0800	7.7	7.3	7.3	7.9
20	0800	7.8	7.3	7.5	8.1
27	0800	7.6	7.3	7.3	7.9

APPENDIX TABLE 8.—*Hydrogen-ion (pH) values in brackish- and fresh-water tanks during salinity-spawning experiment, August 6–September 24, 1959*

Date	Zone time	Tank 1 (brackish water)	Tank 5 (fresh water)	Tap water
Aug. 6	0800	8.3	7.7	8.2
13	0800	8.2	8.3	7.9
20	0800	8.0	8.2	8.1
27	0800	7.7	8.1	7.9
Sept. 3	0800	7.7	7.7	7.9
10	0800	7.6	7.9	8.0
17	0815	7.5	8.1	8.0
24	0800	7.6	8.1	7.9

ENDIX TABLE 9.—*Free carbon dioxide, bicarbonate, and normal carbonate in control and heated tanks during heating experiment and in the fry tank, determined weekly, February 26–August 27, 1959*

[In parts per million]

Date	Zone time	Tank 13 (control)			Tank 14 (heated and covered)			Tank 15 (heated)			Fry tank		
		Free CO_2	Carbonate	Bicarbonate	Free CO_2	Carbonate	Bicarbonate	Free CO_2	Carbonate	Bicarbonate	Free CO_2	Carbonate	Bicarbonate
26	0800	----------	37.6	115.8	----------	----------	----------	----------	----------	----------	----------	----------	----------
5	0805	0.0	40.8	56.4	0.0	----------	----------	0.0	63.8	15.2	0.0	42.6	23.5
12	0800	0.0	7.4	112.6	----------	----------	----------	0.0	13.0	75.3	0.0	32.6	30.1
19	0800	0.0	14.6	111.4	3.8	0.0	136.2	0.0	3.0	93.6	0.0	19.4	37.4
26	0800	8.0	0.0	154.1	6.9	0.0	122.3	5.8	0.0	115.8	0.0	11.4	52.7
2	0800	7.3	0.0	181.7	5.9	0.0	141.6	0.0	5.4	115.4	0.0	3.6	58.9
9	0800	5.5	0.0	173.3	2.0	0.0	65.2	0.0	3.6	104.8	0.0	9.8	60.7
5	0800	----------	0.0	146.4	6.7	0.0	83.4	----------	0.0	123.7	0.0	38.8	23.7
8	0800	5.4	0.0	147.0	6.8	0.0	86.3	----------	----------	----------	----------	----------	----------
0	0810	0.0	2.0	118.4	3.7	0.0	85.5	0.0	----------	130.5	0.0	12.0	57.0
7	0810	2.9	0.0	111.0	3.8	0.0	92.0	----------	0.0	79.3	0.0	7.6	56.7
14	0810	3.9	0.0	117.0	2.7	0.0	85.4	0.0	13.4	59.1	0.0	17.2	42.8
21	0810	5.7	0.0	131.5	----------	0.0	81.0	0.0	----------	82.3	0.0	7.8	55.7
28	0810	4.1	0.0	123.5	2.6	0.0	81.4	0.0	----------	76.6	0.0	29.0	34.0
4	0815	3.8	0.0	115.9	0.0	----------	79.1	0.0	12.2	57.2	0.0	2.4	62.6
11	0815	0.0	----------	----------	----------	----------	----------	0.0	3.8	76.7	0.0	7.4	62.9
18	0810	0.0	26.0	84.3	----------	----------	----------	0.0	10.8	83.8	0.0	16.0	57.7
25	0800	0.0	----------	----------	4.1	0.0	104.3	0.0	16.2	85.0	0.0	32.0	57.1
1	0800	1.2	0.0	73.1	1.4	0.0	116.6	2.2	0.0	77.2	0.0	32.2	46.3
8	0800	0.0	----------	86.5	4.9	0.0	108.0	4.7	0.0	111.7	0.0	15.4	58.3
15	0800	0.0	11.6	74.1	5.8	0.0	128.3	3.8	0.0	107.9	0.0	11.2	60.6
22	0800	1.7	0.0	83.5	5.5	0.0	124.7	4.8	0.0	117.4	2.3	0.0	81.4
29	0800	0.0	24.8	72.8	7.5	0.0	121.4	3.4	0.0	109.2	0.0	36.1	48.8
6	0800	6.5	0.0	180.5	8.5	0.0	117.3	5.2	0.0	115.9	1.2	0.0	76.5
13	0800	1.2	0.0	97.4	11.5	0.0	133.4	6.9	0.0	125.3	2.4	0.0	74.6
20	0800	0.0	17.0	102.8	10.0	0.0	135.0	7.0	0.0	110.7	0.0	66.2	20.6
27	0800	0.0	18.8	97.3	13.3	0.0	140.0	12.7	0.0	149.1	0.0	22.0	59.2

APPENDIX TABLE 10.—*Free carbon dioxide, bicarbonate, and normal carbonate in brackish- and fresh-water tanks during salinity-spawning experiment, August 6–September 24, 1959*

[In parts per million]

Date	Zone time	Tank 1 (brackish water)			Tank 5 (fresh water)		
		Free CO_2	Carbonate	Bicarbonate	Free CO_2	Carbonate	Bicarbonate
Aug. 6	0800	1.7	0.0	94.4	3.5	0.0	111.8
13	0800	0.0	19.1	69.3	0.0	30.6	65.0
20	0800	0.0	14.4	86.7	0.0	24.2	80.1
27	0800	2.6	0.0	123.4	0.0	39.0	71.0
Sept. 3	0800	4.0	0.0	183.3	0.0	80.6	36.3
10	0800	16.2	0.0	188.5	0.0	32.2	81.8
17	0815	8.0	0.0	188.1	0.0	40.0	76.3
24	0800	13.6	0.0	214.0	0.0	54.4	45.3

U.S. GOVERNMENT PRINTING OFFICE: 1962 O—619359